#### AGENDA

REORGANIZATION MEETING OF THE PLANNING COMMISSION OF HAVERFORD TOWNSHIP, THURSDAY, JANUARY 24, 2019 AT 7:00 P.M. IN THE COMMISSIONERS MEETING ROOM, HAVERFORD TOWNSHIP MUNICIPAL SERVICES BUILDING, 1014 DARBY ROAD, HAVERTOWN, PA 19083

Kelly Kirk, D	zzi O mondo mann On	ment		
Item #1 REORGANIZATION/APPOINTMENTS				
A.	Motion to nominate candidates for	or the following seats:		
	(1) Chairman			
(2) Vice-Chairman				
	(3) Secretary			
В.	Motion to appoint	as scribe for the year 2019.		
C. Motion to set the following 2019 calendar of meetings Commission:		calendar of meetings for the Planning		
	January 24 <sup>th</sup> February 14 <sup>th</sup> & 28 <sup>th</sup> March 14 <sup>th</sup> & 28 <sup>th</sup> April 11 <sup>th</sup> & 25 <sup>th</sup> May 9 <sup>th</sup> & 23 <sup>rd</sup> June 13 <sup>th</sup> & 27 <sup>th</sup>	July 25 <sup>th</sup> August 22 <sup>nd</sup> September 12 <sup>th</sup> & 26 <sup>th</sup> October 10 & 24 <sup>th</sup> November 14 <sup>th</sup> December 12 <sup>th</sup>		
	Meetings shall convene at	P.M.		

Item #2 Preliminary/Final Land Development Plan

1400 Lawrence Road- Lynnewood Elementary School

School District of Haverford Township

Item#3- Preliminary/Final Minor Subdivision Plan

1400 Ellston Road

Ormond Properties, LLC

Item#4- Preliminary/Final Minor Subdivision Plan


1417 Fairview Road Ormond Properties, LLC

Item#5- Preliminary/Final Minor Subdivision Plan

217 Walnut Hill Lane Terrador Properties, LLC

Item #6- Approval of Minutes

**ADJOURNMENT** 



REGISTERED PROFESSIONAL 50120-E

DATE: 09/28/18

2 of 28

CALL BEFORE YOU DIG! PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE - STOP CALL 8-1-1

Pennsylvania One Call System, Inc.

1-800-242-1776 8-1-1 (WITHIN PA.)

THE LOCATIONS OF ALL UTILITIES SHOWN ON THE PLANS ARE APPROXIMATE AND MUST BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT PA ONE-CALL AT 811 AT LEAST 3-DAYS BEFORE PROCEEDING WITH ANY EXCAVATION. IT IS ALSO THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN ACCURATE FIELD LOCATIONS OF ALL EXISTING UNDERGROUND AND AERIAL UTILITIES FROM BOTH THE UTILITY COMPANIES AND/OR BY TEST PITS PRIOR TO BEGINNING WORK. ALL UTILITY SERVICES WITHIN THE LIMITS OF WORK MUST ALSO BE FIELD LOCATED PRIOR TO EXCAVATION WORK, CONTRACTORS ARE TO IMMEDIATELY NOTIFY THE ENGINEER OF ANY DEVIATIONS FROM THE PLAN INFORMATION. THE CONTRACTOR SHALL BE RESPONSIBLE TO TAKE ALL PREVENTIVE MEASURES TO PROTECT THE LINES IN ACCORDANCE WITH THE PA ONE-CALL ACT. PA ONE-CALL SERIAL NUMBER 20182762586.

## FLOODPLAIN INFORMATION

SITE LIES WITHIN ZONE X AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN AS SHOW ON FEMA MAP #12045C0104F DATED NOVEMBER 18, 2009.

### SOILS INFORMATION

Me - MADE LAND SCHIST AND GNEISS MATERIALS.

PROP. MON. (4 TYP)

> PROP. PII (2 TYP)

# **ZONING INFORMATION**

30%

45%

40' R/W

TITLE LINE ROAD

R-4 LOW-MED RESIDENTIAL

LOT AREA FRONT YARD SIDE YARD REAR YARD BLDG. COVERAGE IMPERVIOUS COVERAGE

N/L NICHOLAS AND ARLENE CARAMANICO FOLIO NO. 22-09-01992-00

118.67

S64°57'W

LOT 1

S64'57'W 99.81'

S64°57'W R-248.00 119.94'

ELLSTON


REQUIRED **EXISTING** 6,000 S.F. 15,877.77 S.F. 30 FT. 30 FT. 30 FT. 8 FT. MIN., 20 FT. AGG. 17.7 FT. 87.3 FT. 25 FT. 25 FT. 10.9%

24.3%

PROPOSED LOT 1 9,723 S.F. 9.5 FT., 44.6 FT. 17.8% 35.2%

PROPOSED LOT 2 6,154 S.F. 30 FT. 8 FT., 20 FT. AGG. 26.05 FT. 29.3%

42.2%



LOCATION MAP

SCALE: 1" = 300'

### NOTE:

- 1. THE PURPOSE OF THIS PLAN IS TO SUBDIVIDE AN EXISTING PARCEL OF LAND INTO TWO NEW LOTS AND TO CONSTRUCT AND OPERATE A NEW HOUSE AND RELATED APPURTENANCES ON LOT 2. THE EXISTING HOUSE ON LOT 1 IS TO REMAIN WITH 4 PARKING SPACES PROVIDED.
- 2. OUTBOUND INFORMATION AND TOPOGRAPHY ARE BASED ON A SURVEY PERFORMED BY CATANIA ENGINEERING ASSOCIATES ON SEPTEMBER 29, 2018. THE BENCHMARK IS A MANHOLE IN ELLSTON ROAD WITH A RIM ELEVATION. OF 246.00
- 3. PUBLIC WATER, GAS AND SANITARY SEWER ARE PROPOSED.
- 4. ALL NEW UTILITIES SHALL BE PLACED UNDERGROUND.
- 5. ROOF DRAINS FOR THE PROPOSED HOUSE SHALL BE CONNECTED TO THE SEEPAGE BED. BED SHALL BE LOCATED A MINIMUM OF 10 FEET FROM ANY FOUNDATION.
- 6. THE SEEPAGE BED SHALL BE PROTECTED FROM CONSTRUCTION VEHICLES AND CARE SHALL BE TAKEN TO PREVENT THE COMPACTION OF THE SUBGRADE DURING CONSTRUCTION.
- 7. ANY SUBSTANDARD OR DAMAGED CURB OR SIDEWALK SHALL BE REPLACED AS DETERMINED BY THE
- 8. FOR ALL DRIVEWAYS EXCEEDING SIX PERCENT (6%) IN GRADE, A LEVELING AREA OF NOT LESS THAN TWENTY (20) FEET IN LENGTH AND NOT GREATER THAN FOUR PERCENT (4%) IN GRADE SHALL BE PROVIDED AT THE END OF THE DRIVEWAY AT THE STREET LINE. DRIVEWAYS SHALL ALSO HAVE A MINIMUM SLOPE OF 1% AND A MAXIMUM SLOPE OF 12%.
- 9. STREET TREES SHALL BE PLANTED AT LEAST 6 FEET BEHIND RIGHT OF WAY LINES.
- 10. FOUNDATION AS-BUILTS SHALL BE REQUIRED DURING CONSTRUCTION OF THE HOUSES.
- 11. A ROAD OPENING PERMIT SHALL BE REQUIRED FOR THE DRIVEWAY AND UTILITY INSTALLATIONS.
- 12. SANITARY SEWER SERVICE IS NOT PROPOSED FOR THE BASEMENT OF THE PROPOSED HOUSES.
- 13. SAFETY FENCING SHALL BE PLACED AROUND ANY OPEN EXCAVATION, EQUIPMENT OR MATERIALS.
- 14. ANY TREES DAMAGED DURING CONSTRUCTION SHALL BE REPLACED IN ACCORDANCE WITH TOWNSHIP
- 15. ANY CLEANOUTS LOCATED WITHIN A DRIVEWAY SHALL CONTAIN A TRAFFIC RATED COVER.

State of Pennsylvania: County of Delaware :

to be duly recorded.

before me the subscriber, a Notary Public of the Commonwealth of Pennsylvania, residing in \_\_\_\_ personally appeared \_ who being duly sworn according to law, depose and say, that they are the owners or equitable owners of the property shown on this plan, that the said plan was made at their direction and that they acknowledge the same to be their lot and plan and desire the same

On this \_\_\_ day of \_\_\_\_

WITNESS my hand and seal the day and date above written.

Signature of Owner Notary Public My Commission Expires

\_\_\_, a.d., 20\_\_,

REVIEWED THIS \_\_\_\_\_ , 20\_\_\_ , TOWNSHIP ENGINEER APPROVED THIS \_\_\_\_ DAY OF \_\_\_\_ , 20\_\_ , BY THE BOARD OF COMMISSIONERS OF THE TOWNSHIP OF HAVERFORD. AND EXECUTED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_\_\_, 20\_\_\_\_, PRESIDENT \_ SECRETARY APPROVED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_ , 20\_\_\_ , BY THE PLANNING COMMISSION OF HAVERFORD TOWNSHIP. AND EXECUTED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_ CHAIRMAN

\_\_ SECRETARY

N/L EDWARD AND JENNIFER WRIGHT


FOLIO NO. 22-09-00731-00

**LEGEND EXISTING** <u>PROPOSED</u> CONTOURS 350 ————*350*———— SPOT ELEVATIONS x 350.0 x 350.0 SANITARY SEWER SANITARY LATERAL \_\_\_\_ STORM SEWER GAS MAIN WATER MAIN OVERHEAD WIRES RŒ ROCK CONSTRUCTION ENTRANCE DRAINAGE FLOW

GRAPHIC SCALE 1"=20' 20

**PROPERTY** 1200 ELLSTON ROAD TAX MAP#22-37-524 PARID #22-09-00730-00 DEED BOOK/PAGE: 4205/0882 DEED DATE: 6/30/07

**APPLICANT** ORMOND PROPERTIES LLC 2375 WEST CHESTER PIKE BROOMALL, PA. 19008



CATANIA ENGINEERING ASSOCIATES, INC. Consulting Engineers

R.W.M.

TEL. (610) 532-2884 FAX. (610) 532-2923

SUBDIVISION PLAN ORMOND PROPERTIES LLC 1200 ELLSTON ROAD

DELAWARE COUNTY, PA TOWNSHIP OF HAVERFORD 85483-15 J.M.D. DRAWING NO.

CALL BEFORE YOU DIG! PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR

CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE - STOP CALL 8-1-1

Pennsylvania One Call System, Inc.

1-800-242-1776 8-1-1 (WITHIN PA.)

HOUSE NO. 1204

N/L EDWARD AND JENNIFER WRIGHT

FOLIO NO. 22-09-00731-00

258.51

257.43 ,

THE LOCATIONS OF ALL UTILITIES SHOWN ON THE PLANS ARE APPROXIMATE AND MUST BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT PA ONE-CALL AT 811 AT LEAST 3-DAYS BEFORE PROCEEDING WITH ANY EXCAVATION. IT IS ALSO THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN ACCURATE FIELD LOCATIONS OF ALL EXISTING UNDERGROUND AND AERIAL UTILITIES FROM BOTH THE UTILITY COMPANIES AND/OR BY TEST PITS PRIOR TO BEGINNING WORK. ALL UTILITY SERVICES WITHIN THE LIMITS OF WORK MUST ALSO BE FIELD LOCATED PRIOR TO EXCAVATION WORK, CONTRACTORS ARE TO IMMEDIATELY NOTIFY THE ENGINEER OF ANY DEVIATIONS FROM THE PLAN INFORMATION. THE CONTRACTOR SHALL BE RESPONSIBLE TO TAKE ALL PREVENTIVE MEASURES TO PROTECT THE LINES IN ACCORDANCE WITH THE PA ONE-CALL ACT. PA ONE-CALL SERIAL NUMBER 20182762586.

N/L NICHOLAS AND ARLENE CARAMANICO

118.67

\* 258.77

259.23

FOLIO NO. 22-09-01992-00

259.32

258.95 \*

EXISTING HOUSE

1726 S.F. (INCL. PORCH)

119.94

TITLE LINE

NO. 1200

FI OOR- 256 8

257.07

### FLOODPLAIN INFORMATION

SITE LIES WITHIN ZONE X AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN AS SHOW ON FEMA MAP #12045C0104F DATED NOVEMBER 18, 2009.

## SOILS INFORMATION

BC 263.48 263.76

259.89

Me - MADE LAND SCHIST AND GNEISS MATERIALS.

## **ZONING INFORMATION**


R-4 LOW-MED RESIDENTIAL

LOT AREA FRONT YARD SIDE YARD REAR YARD BLDG. COVERAGE IMPERVIOUS COVERAGE

REQUIRED **EXISTING** 6,000 S.F. 15,878 S.F. 30 FT. 30 FT. 8 FT. MIN., 20 FT. AGG. 17.7 FT. 87.3 FT. 25 FT. 10.9% 30% 45% 24.3%

PROPOSED LOT 1 9,723 S.F. 30 FT. 9.5 FT., 44.6 FT. 25 FT. 17.8% 35.2%

PROPOSED LOT 2 6,154 S.F. 30 FT. 8 FT., 20 FT. AGG. 26.05 FT. 29.3% 42.2%




LOCATION MAP

SCALE: 1" = 300'

## NOTE:

- 1. THE PURPOSE OF THIS PLAN IS TO SUBDIVIDE AN EXISTING PARCEL OF LAND INTO TWO NEW LOTS AND TO CONSTRUCT AND OPERATE A NEW HOUSE AND RELATED APPURTENANCES ON LOT 2. THE EXISTING HOUSE ON LOT 1 IS TO REMAIN WITH 4 PARKING SPACES PROVIDED.
- 2. OUTBOUND INFORMATION AND TOPOGRAPHY ARE BASED ON A SURVEY PERFORMED BY CATANIA ENGINEERING ASSOCIATES ON SEPTEMBER 29, 2018. THE BENCHMARK IS A MANHOLE IN ELLSTON ROAD WITH A RIM ELEVATION. OF 246.00
- 3. PUBLIC WATER, GAS AND SANITARY SEWER ARE PROPOSED.
- 4. ALL NEW UTILITIES SHALL BE PLACED UNDERGROUND.
- 5. ROOF DRAINS FOR THE PROPOSED HOUSE SHALL BE CONNECTED TO THE SEEPAGE BED. BED SHALL BE LOCATED A MINIMUM OF 10 FEET FROM ANY FOUNDATION.
- 6. THE SEEPAGE BED SHALL BE PROTECTED FROM CONSTRUCTION VEHICLES AND CARE SHALL BE TAKEN TO PREVENT THE COMPACTION OF THE SUBGRADE DURING CONSTRUCTION.
- 7. ANY SUBSTANDARD OR DAMAGED CURB OR SIDEWALK SHALL BE REPLACED AS DETERMINED BY THE
- 8. FOR ALL DRIVEWAYS EXCEEDING SIX PERCENT (6%) IN GRADE, A LEVELING AREA OF NOT LESS THAN TWENTY (20) FEET IN LENGTH AND NOT GREATER THAN FOUR PERCENT (4%) IN GRADE SHALL BE PROVIDED AT THE END OF THE DRIVEWAY AT THE STREET LINE. DRIVEWAYS SHALL ALSO HAVE A MINIMUM SLOPE OF 1% AND A MAXIMUM SLOPE OF 12%.
- 9. STREET TREES SHALL BE PLANTED AT LEAST 6 FEET BEHIND RIGHT OF WAY LINES.
- 10. FOUNDATION AS-BUILTS SHALL BE REQUIRED DURING CONSTRUCTION OF THE HOUSES.
- 11. A ROAD OPENING PERMIT SHALL BE REQUIRED FOR THE DRIVEWAY AND UTILITY INSTALLATIONS.
- 12. SANITARY SEWER SERVICE IS NOT PROPOSED FOR THE BASEMENT OF THE PROPOSED HOUSES. 13. SAFETY FENCING SHALL BE PLACED AROUND ANY OPEN EXCAVATION. EQUIPMENT OR MATERIALS.
- 14. ANY TREES DAMAGED DURING CONSTRUCTION SHALL BE REPLACED IN ACCORDANCE WITH TOWNSHIP
- 15. ANY CLEANOUTS LOCATED WITHIN A DRIVEWAY SHALL CONTAIN A TRAFFIC RATED COVER.



## EXISTING CONDITIONS/DEMOLITION PLAN

### OWNERS STORMWATER ACKNOWLEDGMENT

I HEREBY ACKNOWLEDGE THAT THE STORMWATER CONTROLS & BMPS ARE FIXTURES THAT CAN NOT BE ALTERED OR REMOVED WITHOUT PRIOR APPROVAL BY THE TOWNSHIP.

OWNERS SIGNATURE

### PRIVATE STORM SEWER AND UNDERGROUND SEEPAGE BED


### INSTALLATION AND MAINTENANCE NOTES:

MAINTENANCE OF THE UNDERGROUND SEEPAGE BED AND PRIVATE STORM SEWER ON EACH LOT WILL BE THE RESPONSIBILITY OF THE INDIVIDUAL HOMEOWNER.
MAINTENANCE ACTIVITIES SHOULD INCLUDE CLEANING THE LEAF GRATES OVER THE DOWNSPOUTS, ROOF GUTTERS, INLET GRATES, ETC.
THE BED SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN HEREIN AND IN ACCORDANCE WITH PLAN DETAILS. CARE SHALL BE TAKEN TO PREVENT COMPACTION OF SUBGRADE AND INSTALLATION SHALL BE SUBJECT TO TOWNSHIP INSPECTION. ONCE INSTALLED AND PERMANENTLY STABILIZED, THE SYSTEM WILL OPERATE UNASSISTED WITH REGULAR MAINTENANCE AS LISTED ABOVE.

I, MICHAEL J. CIOCCO, HEREBY CERTIFY THAT THE DRAINAGE PLAN MEETS ALL DESIGN STANDARDS AND CRITERIA OF THE TOWNSHIP OF HAVERFORD STORMWATER MANAGEMENT ORDINANCE.

GRAPHIC SCALE 20


## **GRADING PLAN LOT 2**



**PROPERTY** 1200 ELLSTON ROAD TAX MAP#22-37-524 PARID #22-09-00730-00 DEED BOOK/PAGE: 4205/0882 DEED DATE: 6/30/07

REQUIREMENTS.

<u>APPLICANT</u> GMG HOLDINGS LLC 2375 WEST CHESTER PIKE BROOMALL, PA. 19008




GRADING PLAN ORMOND PROPERTIES LLC 1200 ELLSTON ROAD

DELAWARE COUNTY, PA TOWNSHIP OF HAVERFORD J.M.D. 85483-15 DRAWING NO

R.W.M.

MICHAEL J CIOCCO, PE

1"=20'



CALL BEFORE YOU DIG!
PENNSYLVANIA LAW REQUIRES

3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE - STOP CALL 8-1-1

Pennsylvania One Call System, Inc.

vania One Call System, Inc. 1-800-242-1776 8-1-1 (WITHIN PA.)

THE LOCATIONS OF ALL UTILITIES SHOWN ON THE PLANS ARE APPROXIMATE AND MUST BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT PA ONE-CALL AT 811 AT LEAST 3-DAYS BEFORE PROCEEDING WITH ANY EXCAVATION. IT IS ALSO THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN ACCURATE FIELD LOCATIONS OF ALL EXISTING UNDERGROUND AND AERIAL UTILITIES FROM BOTH THE UTILITY COMPANIES AND/OR BY TEST PITS PRIOR TO BEGINNING WORK. ALL UTILITY SERVICES WITHIN THE LIMITS OF WORK MUST ALSO BE FIELD LOCATED PRIOR TO EXCAVATION WORK. CONTRACTORS ARE TO IMMEDIATELY NOTIFY THE ENGINEER OF ANY DEVIATIONS FROM THE PLAN INFORMATION. THE CONTRACTOR SHALL BE RESPONSIBLE TO TAKE ALL PREVENTIVE MEASURES TO PROTECT THE LINES IN ACCORDANCE WITH THE PA ONE-CALL ACT. PA ONE-CALL SERIAL NUMBER 20183331333.

State of Pennsylvania:

: County of Delaware

On this \_\_\_ day of \_\_\_\_\_, a.d., 20\_\_, before me the subscriber, a Notary Public of the Commonwealth of Pennsylvania, residing in \_\_\_\_\_, personally appeared \_\_\_\_

who being duly sworn according to law, depose and say, that they are the owners or equitable owners of the property shown on this plan, that the said plan was made at their direction and that they acknowledge the same to be their lot and plan and desire the same to be duly recorded.

WITNESS my hand and seal the day and date above written.

Signature of Owner

Notary Public

My Commission Expires

I, MICHAEL J. CIOCCO, HEREBY CERTIFY THAT THE DRAINAGE PLAN MEETS ALL DESIGN STANDARDS AND CRITERIA OF THE TOWNSHIP OF HAVERFORD STORMWATER MANAGEMENT ORDINANCE.

MICHAEL J CIOCCO, PE

REVIEWED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_\_ , 20\_\_\_ ,

TOWNSHIP ENGINEER

APPROVED THIS \_\_\_\_ DAY OF \_\_\_ , 20\_\_ , BY THE BOARD OF COMMISSIONERS OF THE TOWNSHIP OF HAVERFORD. AND EXECUTED THIS \_\_\_\_ DAY OF \_\_\_\_ , 20\_\_ ,

PRESIDENT
SECRETARY

\_\_\_\_ SECRETARY

APPROVED THIS \_\_\_\_ DAY OF \_\_\_\_ , 20\_\_\_ ,
BY THE PLANNING COMMISSION OF HAVERFORD TOWNSHIP.
AND EXECUTED THIS \_\_\_\_ DAY OF \_\_\_\_\_ , 20\_\_\_ ,
\_\_\_\_ CHAIRMAN

FLOODPLAIN INFORMATION

SITE LIES IN ZONE X AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN AS SHOWN ON FEMA MAP #42045C01014F DATED NOVEMBER 18, 2009.

SOILS INFORMATION

Me - MADE LAND SCHIST AND GNEISS MATERIALS.

### **ZONING INFORMATION**

R-4 LOW-MED RESIDENTIAL

LOT AREA FRONT YARD SIDE YARD REAR YARD BLDG. COVERAGE

6,000 S.F. 42,000 30 FT. 37.5 F 8 FT. MIN., 20 FT. AGG. 34.5 F 25 FT. 227.2 30% 3.4%

REQUIRED

42,000 S.F. 37.5 FT. 34.5 FT./97 FT. AGG. 227.2 FT. 3.4% 8.7%

**EXISTING** 

PROPOSED LOT 1
25,500 S.F.
30 FT.
43 FT.
8 FT./20 FT
217 FT.
7.6%
11.9%

PROPOSED LOT 2
16,500 S.F.
35FT.
43 FT.
8 FT./20 FT.
203 FT.
13.2%
19%



LOCATION MAP

SCALE: 1"=200'

### NOTE:

- 1. THE PURPOSE OF THIS PLAN IS TO SUBDIVIDE AN EXISTING PARCEL OF LAND INTO TWO NEW LOTS, DEMOLISH AN EXISTING HOUSE AND CONSTRUCT AND OPERATE TWO NEW HOUSES AND RELATED APPURTENANCES ON THE TWO NEW LOTS.
- 2. OUTBOUND INFORMATION AND TOPOGRAPHY ARE BASED ON A SURVEY PERFORMED BY CATANIA ENGINEERING ASSOCIATES ON NOVEMBER 26, 2018. THE BENCHMARK IS A MANHOLE IN FAIRVIEW AVE. WITH A RIM ELEVATION. OF 98.09.
- 3. PUBLIC WATER, GAS AND SANITARY SEWER ARE PROPOSED.
- 4. ALL NEW UTILITIES SHALL BE PLACED UNDERGROUND.
- 5. ROOF DRAINS FOR THE PROPOSED HOUSE SHALL BE CONNECTED TO THE SEEPAGE BED. BED SHALL BE LOCATED A MINIMUM OF 10 FEET FROM ANY FOUNDATION.
- 6. THE SEEPAGE BED SHALL BE PROTECTED FROM CONSTRUCTION VEHICLES AND CARE SHALL BE TAKEN TO PREVENT THE COMPACTION OF THE SUBGRADE DURING CONSTRUCTION.
- 7. ANY SUBSTANDARD OR DAMAGED CURB OR SIDEWALK SHALL BE REPLACED AS DETERMINED BY THE TOWNSHIP.
- 8. FOR ALL DRIVEWAYS EXCEEDING SIX PERCENT (6%) IN GRADE, A LEVELING AREA OF NOT LESS THAN TWENTY (20) FEET IN LENGTH AND NOT GREATER THAN FOUR PERCENT (4%) IN GRADE SHALL BE PROVIDED AT THE END OF THE DRIVEWAY AT THE STREET LINE. DRIVEWAYS SHALL ALSO HAVE A MINIMUM SLOPE OF 1% AND A MAXIMUM SLOPE OF 12%.
- 9. STREET TREES SHALL BE PLANTED AT LEAST 6 FEET BEHIND RIGHT OF WAY LINES.
- 10. FOUNDATION AS-BUILTS SHALL BE REQUIRED DURING CONSTRUCTION OF THE HOUSES.
- 11. A ROAD OPENING PERMIT SHALL BE REQUIRED FOR THE DRIVEWAY AND UTILITY INSTALLATIONS.
- 12. SANITARY SEWER SERVICE IS NOT PROPOSED FOR THE BASEMENT OF THE PROPOSED HOUSES.

13. SAFETY FENCING SHALL BE PLACED AROUND ANY OPEN EXCAVATION, EQUIPMENT OR MATERIALS.

- 14. ANY TREES DAMAGED DURING CONSTRUCTION SHALL BE REPLACED IN ACCORDANCE WITH TOWNSHIP REQUIREMENTS.
- 15. ANY CLEANOUTS LOCATED WITHIN A DRIVEWAY SHALL CONTAIN A TRAFFIC RATED COVER.

# PROPERTY

NFORMATION SHOWN ON THIS PLAN IS THE RESU

1"=20'

GRAPHIC SCALE

OF PROFESSIONAL SERVICES RENDERED BY CATANI ENGINEERING ASSOCIATES, INC. REPRODUCTION O

1417 FAIRVIEW AVENUE TAX MAP #22-36-065:000 PARID #22-09-00877-00 APPLICANT

GMG HOLDINGS LLC

2375 WEST CHESTER PIKE

BROOMALL, PA. 19008

THIS PLAN FOR THE PURPOSE OF CREATING ADDITIONAL COPIES OR REVISING PLAN WITHOUT APPROVAL OF CATANIA ENGINEERING ASSOCIATES, INC. IS PROHIBITED. CERTIFICATION FOR THE WORK CONTAINED HEREIN IS LIMITED TO THE ENTITY FOR WHOM THE WORK WAS PERFORMED, AS OF THE DATE SHOWN ON THE PLAN.

NO. DATE

REVISION

DWN. BY

CATANIA ENGINEERING ASSOCIATES, INC.

Consulting Engineers

PRELIMINARY/FINAL SUBDIVISION PLAN

SUBDIVISION PLAN
ORMOND PROPERTIES LLC
FOR
1417 FAIRVIEW AVENUE

CAUTION: TO INSURE VALIDITY OF PLAN

CROSSTRATION SEAL MUST BE IN RED INK.

TO WN SHIP OF HAVERFORD

DELAWARE COUNTY, PA

SCALE 1" = 20' DRAWING NO. 85483-16


CKD. BY M.J.C.

TOWN SHIP OF HAVERFORD

DELAWARE COUNTY, PA

SCALE 1" = 20' DRAWING NO. 85483-16

DATE 11/27/18 SHEET 1 OF 3 SHEETS



# CALL BEFORE YOU DIG!

PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE - STOP CALL 8-1-1

Pennsylvania One Call System, Inc.

1-800-242-1776 8-1-1 (WITHIN PA.)

THE LOCATIONS OF ALL UTILITIES SHOWN ON THE PLANS ARE APPROXIMATE AND MUST BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT PA ONE-CALL AT 811 AT LEAST 3-DAYS BEFORE PROCEEDING WITH ANY EXCAVATION. IT IS ALSO THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN ACCURATE FIELD LOCATIONS OF ALL EXISTING UNDERGROUND AND AERIAL UTILITIES FROM BOTH THE UTILITY COMPANIES AND/OR BY TEST PITS PRIOR TO BEGINNING WORK. ALL UTILITY SERVICES WITHIN THE LIMITS OF WORK MUST ALSO BE FIELD LOCATED PRIOR TO EXCAVATION WORK. CONTROL OF THE ENGINEER OF ANY DEMANDER OF THE ENGINEER OF THE ENGI THE ENGINEER OF ANY DEVIATIONS FROM THE PLAN INFORMATION. THE CONTRACTOR SHALL BE RESPONSIBLE TO TAKE ALL PREVENTIVE MEASURES TO PROTECT THE LINES IN ACCORDANCE WITH THE PA ONE-CALL ACT. PA ONE-CALL SERIAL NUMBER 20183331333.

**LEGEND EXISTING** <u>PROPOSED</u> CONTOURS SPOT ELEVATIONS x 350.0 x 350.0 \_\_\_\_5 \_\_\_\_ SANITARY SEWER SANITARY LATERAL CO. CLEANOUT STORM SEWER GAS MAIN WATER MAIN WATER VALVE OVERHEAD ELECTRIC ELECTRIC SUPER FILTER FABRIC FENCE (36") ROCK CONSTRUCTION ENTRANCE DRAINAGE FLOW STEEP SLOPES 15%-25%

### OWNERS STORMWATER ACKNOWLEDGMENT

I HEREBY ACKNOWLEDGE THAT THE STORMWATER CONTROLS & BMPS ARE FIXTURES THAT CAN NOT BE ALTERED OR REMOVED WITHOUT PRIOR APPROVAL BY THE TOWNSHIP.

OWNERS SIGNATURE

### PRIVATE STORM SEWER AND UNDERGROUND SEEPAGE BED INSTALLATION AND MAINTENANCE NOTES:

MAINTENANCE OF THE UNDERGROUND SEEPAGE BED AND PRIVATE STORM SEWER ON EACH LOT WILL BE THE RESPONSIBILITY OF THE INDIVIDUAL HOMEOWNER. MAINTENANCE ACTIVITIES SHOULD INCLUDE CLEANING THE LEAF GRATES OVER THI DOWNSPOUTS, ROOF GUTTERS, INLET GRATES, ETC. THE BED SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN HEREIN AND IN ACCORDANCE WITH PLAN DETAILS. CARE SHALL BE TAKEN TO PREVENT COMPACTION OF SUBGRADE AND INSTALLATION SHALL BE SUBJECT TO TOWNSHIP INSPECTION. ONCE INSTALLED AND PERMANENTLY STABILIZED, THE SYSTEM WILL OPERATE UNASSISTED WITH REGULAR MAINTENANCE AS LISTED ABOVE.

MICHAEL J. CIOCCO, HEREBY CERTIFY THAT THE DRAINAGE PLAN MEETS ALL DESIGN STANDARDS AND CRITERIA OF THE TOWNSHIP OF HAVERFORD STORMWATER MANAGEMENT ORDINANCE.

### **FLOODPLAIN INFORMATION**

SITE LIES IN ZONE X AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN AS SHOWN ON FEMA MAP #42045C01014F DATED NOVEMBER 18, 2009.

### SOILS INFORMATION

# Me - MADE LAND SCHIST AND GNEISS MATERIALS. EX. INLET TG 96.20 INV. 90.7 INV. 89.7 102.48 + 96.63 TO HAVCREST CIR. + 101.10 330'± TO FOREST AVE. + 96.80 + 101.10 103.28 103.44 PORCH TBR FF 105.73 EX. HOUSE 1128 S.F. **TBR** 102.99 102.64 EX. HOUSE #1413 93.03 4 101.48 GARAGE WOOD DECK FF 101.43 + 99.53 SUBRAMANIAN MCGOVERN TAX MAP #22-36-066 Y MAP #22-36-064 102.63 GRASS 2" + 97.45 102.74 98.63 } + 98.71 + 102.83 + 100.39

## EXISTING CONDITIONS/DEMOLITION PLAN

X 96.16

S 64'57' W

MARANO

TAX MAP #22-36-073

1428 PARKSIDE DR.

BONHAGE

TAX MAP #22-36-074

1432 PARKSIDE DR.

BURKE

TAX MAP #22-36-073-1

1424 PEAKSIDE DR.

+ + + 99.5

+ 101.38

+ 99.64

TAX MAP #22-36-072

1420 PARKSIDE DR.

140.0099.0

+ 98.26

### **ZONING INFORMATION**

R-4 LOW-MED RESIDENTIAL

TOPSOIL STOCKPII

LOT AREA FRONT YARD SIDE YARD REAR YARD

BLDG. COVERAGE

IMPERVIOUS COVERAGE

INV. 89.7

PROTECTION~

TO HAVCREST CIR.

PROP. STREET

TREE (3 TYP)

#1425

GARAGE

MCGOVERN

TAX MAP #22-36-064

BONHAGE

TAX MAP #22-36-074

1432 PARKSIDE DR.

REQUIRED 6,000 S.F. 30 FT.MIN. (MEDIAN) 8 FT. MIN., 20 FT. AGG. 25 FT. MIN. 30% 3.4% 45% 8.7%

LIMIT OF DISTURBANCE

AREA = 20,742 S.F./0.48 AC.

RCD

20', 100.95

PROP.DRIVE

GARAGE

14'x16' 224 S.I

PROP. SEEPAGE

YD **#2**'x26'x5'

G 100.5

LOT 1

85.00

MARANO

TAX MAP #22-36-073

1428 PARKSIDE DR.

S 6457' W

WOODED

VINYL FENCE

GRADING PLAN

BURKE

TAX MAP #22-36-073-1

1424 PEAKSIDE DR.

GF 102.3

PROP. HOUSE

1931 S.F.

#2201

FF=104.3

**EXISTING** 42,000 S.F. 37.5 FT. 34.5 FT./97 FT. AGG. 227.2 FŤ.

CONNECTIONS

PROPOSED LOT 25,500 S.F. 30 FT. 8 FT./20 FT 217 FT. 7.6% 11.9%

/MATCH EX. PAVING

330'± TO FOREST AVE.

EX. HOUSE

. WOOD DECK

SUBRAMANIAN

■ TAX MAP #22-36-066

- CONSTRUCTION

GRASS

TEMP.

**FENCE** (TYP)

#1413

REUSE EXIST. UTILITY PROP. DEP. CURB (TYP)

GARAGE

GF=104.3

PROP. HOUSE

YB #3 TG 100.4

LOT 2

2,170 S.F. FF=106.3

DECK/PATIO

12'x17'

204 S.F.

YD #2 TG 99.0

16,500 S.F. 35FT. 43 FT. 8 FT./20 FT. 203 FT. 13.2% 19%

PROPOSED LOT 2



### LOCATION MAP SCALE: 1"=200'

### WAIVERS REQUESTED

1. SECTION 160-4.A - TO ALLOW A WAIVER OF THE TWO STEP PLAN REVIEW PROCESS AND ALLOW THE PLAN TO BE CONSIDERED IN THE FINAL REVIEW STAGE.

TOWNSHIP.

- 1. THE PURPOSE OF THIS PLAN IS TO SUBDIVIDE AN EXISTING PARCEL OF LAND INTO TWO NEW LOTS, DEMOLISH AN EXISTING HOUSE AND CONSTRUCT AND OPERATE TWO NEW HOUSES AND RELATED APPURTENANCES ON THE TWO NEW LOTS.
- 2. OUTBOUND INFORMATION AND TOPOGRAPHY ARE BASED ON A SURVEY PERFORMED BY CATANIA ENGINEERING ASSOCIATES ON NOVEMBER 26, 2018. THE BENCHMARK IS A MANHOLE IN FAIRVIEW AVE. WITH A RIM ELEVATION. OF 98.09.
- 3. PUBLIC WATER, GAS AND SANITARY SEWER ARE PROPOSED.
- 4. ALL NEW UTILITIES SHALL BE PLACED UNDERGROUND.
- 5. ROOF DRAINS FOR THE PROPOSED HOUSE SHALL BE CONNECTED TO THE SEEPAGE BED. BED SHALL BE LOCATED A MINIMUM OF 10 FEET FROM ANY FOUNDATION.
- 6. THE SEEPAGE BED SHALL BE PROTECTED FROM CONSTRUCTION VEHICLES AND CARE SHALL BE
- TAKEN TO PREVENT THE COMPACTION OF THE SUBGRADE DURING CONSTRUCTION. 7. ANY SUBSTANDARD OR DAMAGED CURB OR SIDEWALK SHALL BE REPLACED AS DETERMINED BY THE
- 8. FOR ALL DRIVEWAYS EXCEEDING SIX PERCENT (6%) IN GRADE, A LEVELING AREA OF NOT LESS THAN TWENTY (20) FEET IN LENGTH AND NOT GREATER THAN FOUR PERCENT (4%) IN GRADE SHALL BE PROVIDED AT THE END OF THE DRIVEWAY AT THE STREET LINE. DRIVEWAYS SHALL ALSO HAVE A MINIMUM SLOPE OF 1% AND A MAXIMUM SLOPE OF 12%.
- 9. STREET TREES SHALL BE PLANTED AT LEAST 6 FEET BEHIND RIGHT OF WAY LINES.
- 10. FOUNDATION AS-BUILTS SHALL BE REQUIRED DURING CONSTRUCTION OF THE HOUSES.
- 11. A ROAD OPENING PERMIT SHALL BE REQUIRED FOR THE DRIVEWAY AND UTILITY INSTALLATIONS
- 12. SANITARY SEWER SERVICE IS NOT PROPOSED FOR THE BASEMENT OF THE PROPOSED HOUSES.
- 13. SAFETY FENCING SHALL BE PLACED AROUND ANY OPEN EXCAVATION, EQUIPMENT OR MATERIALS.
- 14. ANY TREES DAMAGED DURING CONSTRUCTION SHALL BE REPLACED IN ACCORDANCE WITH TOWNSHIP REQUIREMENTS.
- 15. ANY CLEANOUTS LOCATED WITHIN A DRIVEWAY SHALL CONTAIN A TRAFFIC RATED COVER.

### TREE REPLACEMENT REQUIREMENTS


EXISTING TREES TO BE REMOVED WITHIN THE TREE PROTECTION ZONE = 0 TOTAL TREE REPLACEMENT REQUIRED = 0

PLANTING SCHEDULE - PROP. STREET TREE					
KEY	BOTANICAL NAME COMMON NAME	QUANTITY	SIZE	REMARKS	
OG	OCTOBER GLORY ACER RUBUM OCTOBER GLORY	3	3" CALIPER	В&В	

## **PROPERTY** 1417 FAIRVIEW AVENUE

TAX MAP #22-36-065:000 PARID #22-09-00877-00

<u>APPLICANT</u> GMG HOLDINGS LLC 2375 WEST CHESTER PIKE BROOMALL, PA. 19008



# ANIA ENGINEERING ASSOCIATES, INC. Consulting Engineers

KD. BY M.J.C.

520 WEST MacDADE BOULEVARD MILMONT PARK, PA. 19033-3311 TEL. (610) 532-2884 FAX. (610) 532-2923

PRELIMINARY/FINAL GRADING PLAN ORMOND PROPERTIES LLC

1417 FAIRVIEW AVENUE DELAWARE COUNTY, PA TOWNSHIP OF HAVERFORD 1" = 20' 11/27/1885483-16 <u>J.M.D.</u> DRAWING NO.

1"=20' GRAPHIC SCALE

55.00'

GARAGE N/L


DITROLIO


TAX MAP #22-36-072

1420 PARKSIDE DR.

140.0Ô

MICHAEL J CIOCCO, PE





0.0% | 190 S.F. |

LOT #2

13,750

1,685

615

2,600

18.9%

LANDS N/L

STEPHEN & MAUREEN

*MCCROSSIN* 

229 WALNUT HILL LN

FOLIO NUMBER: 22-09-02563-00 /

LOT 2

13,750 S.F.

0.3157 AC.

0 | 0.0% | 140 S.F. | 4.8%

|EXISTING | PROPOSED | PROPOSED

LOT #1

7,500

1,065

190

135

325

1,715

22.9%

14.2%

PARCEL

21,250

1,065

190

175

370

1,800

8.5%

5.0%

SETBACK TO BUILDING

35.6' OFF RIGHT-OF-WAY

38.6' OFF RIGHT-OF-WAY

38.6' OFF RIGHT-OF-WAY

35.6' OFF RIGHT-OF-WAY

39.6' OFF RIGHT-OF-WAY

34.6' OFF RIGHT-OF-WAY

32.6' OFF RIGHT-OF-WAY

40.6' OFF RIGHT-OF-WAY

34.6' OFF RIGHT-OF-WAY

37.6' OFF RIGHT-OF-WAY

34.6' OFF RIGHT-OF-WAY

MEDIAN SETBACK 36.6' OFF RIGHT-OF-WAY

WAIVERS NOTE: A) WAIVER IS REQUESTED FROM THE CODE OF THE TOWNSHIP OF HAVERFORD CHAPTER 160 SECTION 5B. (3)(j) REGARDING

- A MINIMUM RIGHT OF WAY WIDTH OF 50 FEET AND CARTWAY OF 25 FEET FOR WALNUT HILL LN. IF REQUIRED. THE EXISTING RIGHT OF WAY AND CARTWAY WIDTHS ARE 48 AND 24 FEET RESPECTIVELY.
- B) A WAIVER IS REQUESTED FROM THE CODE OF THE HAVERFORD TOWNSHIP CHAPTER 160 SECTION 4.A. REGARDING THE TWO STEP REVIEW PROCESS. C) A WAIVER IS REQUESTED FROM THE CODE OF THE HAVERFORD TOWNSHIP CHAPTER 170 SECTION 2.H. REGARDING THE
- STREET TREE REQUIREMENTS. D) A WAIVER IS REQUESTED FROM THE CODE OF THE HAVERFORD TOWNSHIP CHAPTER 170 SECTION 8.A.(1) REGARDING THE

### VARIANCE NOTE:

A) ZONING VARIANCE WAS GRANTED BY THE ZONING HEARING BOARD ON DECEMBER 9, 2018 FROM THE CODE OF THE TOWNSHIP OF HAVERFORD CHAPTER 182 SECTION 207. C.(6)(a) REGARDING A MINIMUM SIDE YARD WIDTH OF 8 FOOT. THE EXISTING SIDE YARD WIDTH IS 7.2'.


7,500 S.F.

0.1722 AC.


She She

ANTHONY W & LIŚA YACOVELLI

215 WALNUT HILL LN FOLIO NUMBER: 22-09-02561-00



ENERAL NOTES:



SITE AREA: 21,250 S.F. = 0.4878 AC. SITE IS ZONED R-5 RESIDENTIAL. REQUIREMENTS: LOT SIZE: 5,500 S.F. (MIN.) STREET FRONTAGE: 38 FT. (MIN.) LOT WIDTH AT BUILDING LINE: 50 FT. (MIN.)

SITE IS NOT LOCATED IN FLOOD HAZARD AREA.

BUILDING COVERAGE: 30% (MAX.) FRONT YARD: 30 FT. (MIN.) REAR YARD: 25 FT. (MIN.)

SIDE YARDS: 8 FT. (MIN. EACH); 16 FT. (MIN. AGGREGATE) BUILDING HEIGHT: 35 FT. (MAX.) IMPERVIOUS SURFACE RATIO: 45% (MAX.)

SITE IS SERVICED BY PUBLIC WATER AND SANITARY SEWER SERVICE. EXISTING SOIL TYPE: Me-MADE LAND, SCHIST AND GNEISS MATERIALS. BENCHMARK REFERENCE: TAKEN ON INVERT OF SANITARY SEWER MANHOLE ON WALNUT HILL LANE SOUTHWEST OF WINDSOR PARK LANE AS SHOWN ON "EROSION CONTROL PLAN - SECTION 2 PROPOSED SUBDIVISION FOR KEN LIZ CORPORATION, INC. PLAN PREPARED BY H. E MacCOMBIE, JR., P.E. CONSULTING ENGINEER PLAN DATED FEBRUARY 22 1977 AND LAST REVISED APRIL 11, 1977. INVERT ELEVATION = 254.03. PRIOR TO THE START OF ANY CONSTRUCTION, DEMOLITION OR EXCAVATION THE CONTRACTOR SHALL HAVE THE LOCATION OF ALL UNDERGROUND UTILITIES WITHIN THE AREA OF WORK VERIFIED IN THE FIELD IN ACCORDANCE WITH PA. ACT 287 OF 1974 AS AMENDED BY PA

ACT 50 OF 2017, 73 P.S. SECTION 176 ET, SEQ. KNOWN AS THE "UNDERGROUND UTILITY LINE PROTECTION LAW", THROUGH THE ONE CALL SYSTEM. NOTIFICATION SHALL BE NOT LESS THAN THREE NOR MORE THAN TEN BUSINESS DAY IN ADVANCE OF THE START OF WORK. PENNSYLVANIA ONE CALL SYSTEM - 1-800-242-1776 OR 8-1-1. 8. A COPY OF THIS APPROVED PLAN MUST BE AVAILABLE ON-SITE AT ALL TIMES DURING CONSTRUCTION IN ACCORDANCE WITH STATE LAW. 9. ANY CONSTRUCTION OR GRADING TO BE DONE SHALL BE DONE IN

ACCORDANCE WITH TOWNSHIP OF HAVERFORD EROSION AND SEDIMENT CONTROL ORDINANCE No. 1505. 10. EXTREME CARE SHALL BE UNDERTAKEN DURING THE CONSTRUCTION OF THE PROPOSED DEVELOPMENT IN ORDER TO PROTECT THE HEALTH AND VIGOR OF THE EXISTING TREES LOCATED WITHIN THE TREE PROTECTION ZONE AS OUTLINED IN HAVERFORD TOWNSHIP ORDINANCE No. 1680,

SECTION II, PARAGRAPH 8. 11. DURING CONSTRUCTION THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING AND MAINTAINING TEMPORARY EROSION CONTROL MEASURES AND PERMANENT STORMWATER MANAGEMENT FACILITIES. AFTER CONSTRUCTION THE HOMEOWNER IS RESPONSIBLE FOR MAINTAINING STORMWATER MANAGEMENT FACILITIES. 12. A STORMWATER CONTROL AND BMP OPERATION AND MAINTENANCE

AGREEMENT MUST BE SIGNED AND RECORDED. A CONTRIBUTION OF \$2,200 MUST BE MADE TO THE MUNICIPAL STORMWATER CONTROL AND BMP OPERATION AND MAINTENANCE FUND. THE OPERATION AND MAINTENANCE AGREEMENT AND CONTRIBUTION TO THE MUNICIPAL STORMWATER CONTROL AND BMP OPERATIONAL FUND ARE REQUIRED FOR EACH INDIVIDUAL LOT TO BE DEVELOPED.

13. AN EROSION AND SEDIMENT CONTROL PERMIT FROM THE TOWNSHIP WILL BE REQUIRED FOR EACH LOT PRIOR TO CONSTRUCTION. 14. ANY SUBSTANDARD OR DAMAGED CURB AND SIDEWALK SHALL BE

REPLACED IN ACCORDANCE WITH TOWNSHIP REQUIREMENTS. 15. THE LATERAL CONNECTION DETAILS SHOULD BE REVIEWED BY THE TOWNSHIP PLUMBING INSPECTOR. 16. A DRAINAGE PLAN APPLICATION AND CHECKLIST SHALL BE SUBMITTED

FOR EACH LOT AT THE TIME OF GRADING, DRAINAGE, SOIL EROSION AND SEDIMENTATION CONTROL PERMIT APPLICATION. 17. CLEANOUTS SHALL BE PROVIDED AT THE PIPE ENDS WITHIN THE

PROPOSED INFILTRATION BEDS FOR MAINTENANCE. 18. ALL ROOF DRAIN PIPES SHALL BE SCHEDULE 40 PIPE OR BETTER. 19. ALL PROPOSED MONUMENTS SHALL BE CONCRETE. 20. ALL PERIMETER SILT FENCE SHALL BE SUPER SILT FENCE.


21. PROVIDE "NDS" SUMP BOX WITH DEBRIS TRAP ON ROOF DRAINS WHICH DO NOT DRAIN TO CATCH BASINS. 22. INFILTRATION AREA SHALL BE FENCED OFF AND PROTECTED FROM COMPACTION DURING CONSTRUCTION AS SHOWN ON THE PLAN.

### RECORD OWNER

ANNE & PATRICE LOPATIN 217 WALNUT HILL LN HAVERTOWN, PA 19083 FOLIO NUMBER: 22-09-02562-00 MAP NUMBER: 22-31 -763:000

### <u>APPLICANT</u>

TERRADOR PENN LLC C/O JOSEPH DORAZIO 2111 DARBY ROAD HAVERTOWN, PA 19083



F.F.


NOTE:
VERTICAL TEXT INDICATES PROPOSED FEATURES

SLANTED TEXT INDICATES EXISTING FEATURES

(T.B.R.)

DATE

F.F.



PLAN OF SUBDIVISION <u>FOR</u> TERRADOR PENN LLC.

217 WALNUT HILL LN.

DELAWARE COUNTY, PA SEPTEMBER 21, 2018

HERBERT E. MacCOMBIE, JR., P.E. CONSULTING ENGINEERS AND SURVEYORS, INC. P.O. BOX 118

REVIEWED BY THE DELAWARE COUNTY PLANNING COMMISSION DATE: COMMONWEALTH OF PENNSYLVANIA) ATTEST:\_ DCPD No.\_\_\_\_\_ WHO BEING DULY SWORN ACCORDING TO LAW, DEPOSES AND SAYS THAT APPROVED THIS \_\_\_\_\_DAY OF \_\_\_\_\_, \_\_\_\_ BY THE HARVERFORD TOWNSHIP PLANNING COMMISSION THEY ARE THE OWNERS OR EQUITABLE OWNERS OF THE PROPERTY SHOWN ON THIS PLAN, THAT THE SUBDIVISION PLAN THEREOF WAS ATTEST . MADE AT THEIR DIRECTION AND THAT THEY ACKNOWLEDGED THE SAME (CHAIRMAN) (SECRI TO BE THEIR ACT AND DESIRES THE SAME TO BE RECORDED AS SUCH ACCORDING TO LAW. BY THE HARVERFORD TOWNSHIP BOARD OF COMMISSIONERS. WITNESS MY HAND AND SEAL THE DAY AND DATE WRITTEN ABOVE ATTEST (PRESIDENT) (TOWNSHIP SECRETARY) (OWNER'S SIGNATURE(S)) REVIEWED BY THE HARVERFORD TOWNSHIP ENGINEER MY COMMISSION EXPIRES \_\_\_\_\_\_

THIS PLAN SHALL BE A BLACKLINE PRINT WITH A RED OR GREEN REGISTRATION SEAL TO BE CONSIDERED A VALID PLAN. REPRODUCTION OF THIS PLAN FOR ANY PURPOSE WITHOUT THE APPROVAL OF HERBERT E. MacCOMBIE, JR. P.E. CONSULTING ENGINEERS AND SURVEYORS, INC. IS STRICTLY PROHIBITED.

December 27, 2018 1:30 PM

STEEP SLOPES DISTURBED 15%-25% (S.F.)

BUILDING AND IMPERVIOUS COVERAGES

Lot area (S.F.)

Patio/ Deck/Steps/ Walls

MEDIAN SETBACK

ADDRESS

205 WALNUT LN.

207 WALNUT LN.

209 WALNUT LN.

211 WALNUT LN.

213 WALNUT LN.

215 WALNUT LN.

227 WALNUT LN.

229 WALNUT LN.

231 WALNUT LN.

233 WALNUT LN.

235 WALNUT LN.

Total Impervious

Building Coverage

Impervious coverage

Building

Walks

Driveway

VERY STEEP SLOPES DISTURBED >25% (S.F.)

BROOMALL, PA. 19008

SHEET 1 OF 8 HAVERFORD FILE #586 CADD FILE PS1\_Walnut\_Hill\_Ln.dwg

REVISION

TO BE REMOVED

FINISHED FLOOR

### CONSTRUCTION SEQUENCE: . PLACE AND PROPERLY SECURE SILT BARRIER FENCE AT THE LOCATIONS SHOWN ON PLAN. CHECK SILT BARRIER FENCE WEEKLY AND AFTER EACH RUNOFF EVENT FOR SERVICEABILITY. REPAIR OR REPLACE ANY DAMAGED SECTIONS AS REQUIRED. PLACE STONE TIRE CLEANING STRIP AT PROPOSED DRIVEWAY ACCESS FOR FULL WIDTH OF DRIVEWAY TO ACT AS A SEDIMENT FILTER TRAP FOR TRUCK EGRESS. USE AASHTO #1 STONE 12" STRIP TOP SOIL AND STOCKPILE AT THE LOCATION SHOWN ON THE PLAN, FOR FUTURE USE. PLACE SILT FENCE AROUND TOP SOIL STOCKPILE. I. EXCAVATE FOR PROPOSED BUILDING FOOTINGS. STOCKPILE EXCAVATED GENERAL SOIL MATERIAL TO THE FRONT OF THE PROPOSED BUILDING. . CONSTRUCT FOOTINGS AND FOUNDATION WALLS TO THE PROPER ELEVATIONS AND BACKFILL AROUND WALLS TO FINAL GRADE. REMOVE ANY EXCESS EXCAVATED MATERIAL FROM SITE. CONSTRUCT PROPOSED STORMWATER MANAGEMENT FACILITIES AT THE LOCATION AND GRADE SHOWN ON PLAN. TAP ROOF DRAINS AS NOTED DIRECTLY INTO THE SPREAD BASIN OR CATCH BASIN. PROVIDE "T" SECTIONS AT DOWNSPOUTS TO PROVIDE FOR OVERFLOW RELIEF TO DISCHARGE ONTO CONCRETE SPLASH PADS. NEWLY CONSTRUCTED INLETS OR CATCH BASINS SHALL BE PROTECTED IN ACCORDANCE WITH DETAIL ON PLAN. ALL EXCESS EXCAVATED GENERAL SOIL IS TO BE REMOVED FROM SITE TO AN APPROVED 10. CONSTRUCT PROPOSED UTILITY TIE-INS. PLACE DRIVEWAY STONE BASE AND ROUGH GRADE. 1. PAVE PROPOSED DRIVEWAY AND STABILIZE ALL EXPOSED AREAS WITH SOD AND/OR SEEDING AND SOIL SUPPLEMENTS, FORMULA B, PROTECT SEEDED AREAS WITH HAY OR MULCH COVERING. 12. TEMPORARY SEEDING IS TO BE APPLIED TO ALL AREAS WHICH WILL REMAIN OPEN FOR LONGER THAN 20 DAYS PRIOR TO PERMANENT GRADING AND SEEDING OR SODDING. USE FORMULA E SEEDING AND SOIL SUPPLEMENTS. 13. REMOVE SILT BARRIER FENCE AND INLET/CATCH BASIN PROTECTION ONLY AFTER ALL EXPOSED AREAS HAVE BEEN STABILIZED.

### OPERATION AND MAINTENANCE PROCEDURES

THE FOLLOWING MEASURES SHOULD BE CHECKED AND/OR PERFORMED ON A QUARTERLY BASIS BY

- . IT SHALL BE THE RESPONSIBILITY OF EACH INDIVIDUAL PROPERTY OWNER TO MAINTAIN ANY STORMWATER MANAGEMENT FACILITIES LOCATED ON HIS/HER RESPECTIVE LOT INCLUDING. BUT NOT LIMITED TO, CATCH BASINS, INLETS, INFILTRATION BASINS, DIVERSION CHANNELS, COLLECTION CHANNELS, ROOF DRAINS, STORM SEWERS, CLEAN-OUTS AND SUMPS.
- . CATCH BASINS SHOULD BE CLEANED ON A QUARTERLY BASIS OF ANY ACCUMULATED DEBRIS AND SEDIMENT. INFLOW AND OUTFLOW POINTS INTO THE INDIVIDUAL ON-LOT SYSTEMS SHOULD BE KEPT CLEAR OF LEAVES AND OTHER DEBRIS. ANY LEAVES OR DEBRIS WILL NEGATIVELY IMPACT THE PERFORMANCE OF THESE SYSTEMS.
- ROOF DRAINS SHOULD BE CLEANED SEASONALLY.
- 4. ALL DIVERSION CHANNELS AND COLLECTION CHANNELS SHOULD BE MAINTAINED AT ALL TIMES WITH A GOOD STAND OF VEGETATION AND NOT ALTERED BY THE PROPERTY OWNER.

#### POST CONSTRUCTION STORMWATER BMP OPERATION AND MAINTENANCE PROCEDURES

THE FOLLOWING BMPS SHOULD BE CHECKED AS INDICATED BELOW BY THE RESPONSIBLE PARTY INDICATED IN OPERATION AND MAINTENANCE AGREEMENT REVIEWED AND APPROVED BY THE

**GRASS SWALES** 

GRASS SWALES/CHANNELS SHALL BE MAINTAINED WITH GRASS. THE SWALES SHALL BE MOWED AT 2 1/2" TO 3" HIGH. GRASS SWALES SHALL BE WEEDED TO REMOVE INVASIVES. TRASH AND DEBRIS SHALL BE REMOVED FROM THE SWALES IMMEDIATELY. IF EROSION OCCURS UPHILL OF THE SWALE, ANY SEDIMENT DEPOSITED IN THE SWALE SHALL BE REMOVED IMMEDIATELY. THE ERODED AREAS SHOULD BE REPAIRED AND STABILIZED WITH SEED AND MULCH. APPLY SEED AND MULCH TO DISTURBED AREAS OF THE SWALES AFTER SEDIMENT IS REMOVED. GRASS SWALES SHALL BE MAINTAINED BY THE RESPONSIBLE PARTY INDICATED IN THE OPERATION AND MAINTENANCE AGREEMENT REVIEWED AND APPROVED BY THE TOWNSHIP.

### UNDERGROUND INFILTRATION BASINS

INFILTRATION BASINS, INLET GRATES, AND THE SUMP IN THE UPSTREAM INLET SHALL BE INSPECTED QUARTERLY AND AFTER EACH MAJOR STORM. LEAVES AND OTHER DEBRIS SHALL BE REMOVED IMMEDIATELY. CHECK THE UPSTREAM AND DOWNSTREAM STORM SEWER STRUCTURES FOR SEDIMENT ACCUMULATION OR STANDING WATER. CLEAN THE SEDIMENT FROM THE BOTTOM OF THE STRUCTURES AND DISPOSE OF IN AN APPROVED MANNER. INSPECTIONS, OPERATION. MAINTFNANCE. AND REPAIRS TO THE UNDERGROUND INFILTRATION BASIN SHALL BE THE RESPONSIBILITY OF THE OWNER AND APPROVED BY THE TOWNSHIP.

CATCH BASINS, INLET GRATES AND THE SUMP IN THE UPSTREAM INLET SHALL BE INSPECTED QUARTERLY AND AFTER EACH MAJOR STORM. LEAVES AND OTHER DEBRIS SHALL BE REMOVED IMMEDIATELY. CLEAN THE SEDIMENT FROM THE BOTTOM OF THE STRUCTURES AND DISPOSE OF IN

## SEDIMENTATION AND EROSION CONTROL MEASURES

- SHOULD UNFORESEEN EROSIVE CONDITIONS DEVELOP DURING CONSTRUCTION, THE CONTRACTOR SHALL TAKE ACTION TO REMEDY SUCH CONDITIONS AND TO PREVENT DAMAGE TO ADJACENT PROPERTIES AS A RESULT OF INCREASED RUNOFF AND/OR SEDIMENT DISPLACEMENT. STOCKPILES OF WOOD CHIPS, HAY BALES, CRUSHED STONE AND OTHER MULCHES SHALL BE HELD IN READINESS TO DEAL IMMEDIATELY WITH EMERGENCY PROBLEMS OF EROSION. THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE
- PROVISIONS OF APPENDIX 64, EROSION CONTROL RULES AND REGULATIONS, TITLE 25, PART 1, DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUB-PART C, PROTECTION OF NATURAL RESOURCES, ARTICLE III, WATER RESOURCES, CHAPTER 102, EROSION CONTROL. A COPY OF THIS EROSION AND SEDIMENTATION CONTROL PLAN MUST BE POSTED AT
- THE CONSTRUCTION SITE IN ACCORDANCE WITH STATE LAW. EROSION CONTROL BLANKET & FORMULA B SEEDING SHALL BE PLACED IN SWALES, DIVERSIONS AND CHANNELS OF CONVEYANCE WHICH WILL BE RECEIVING WATER IMMEDIATELY AFTER CONSTRUCTION. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND
- SEDIMENTATION CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE CONTROLS MUST BE STABILIZED.
- . UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENTATION CONTROLS MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION CONTROLS AFTER EACH STORM EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND
- RENETTING MUST BE PERFORMED IMMEDIATELY. THE DEVELOPER WILL BE RESPONSIBLE FOR THE PROPER CONSTRUCTION. STABILIZATION, AND MAINTENANCE OF ALL EROSION AND SEDIMENTATION CONTROLS
- AND RELATED ITEMS INCLUDED WITHIN THIS PLAN. SHOULD ANY MEASURES CONTAINED WITHIN THIS PLAN PROVE INCAPABLE OF ADEQUATELY REMOVING SEDIMENT FROM ON-SITE FLOWS PRIOR TO DISCHARGE OR OF STABILIZING THE SURFACES INVOLVED, ADDITIONAL MEASURES MUST BE IMMEDIATELY IMPLEMENTED BY THE DEVELOPER TO ELIMINATE ALL SUCH PROBLEMS.

### TREE REPLACEMENT TABULATION:

COMPENSATORY PLANTING TABULATION. CODE OF THE TOWNSHIP OF HAVERFORD CHAPTER 170 SECTION 8.A.(1): 1" OF REPLACEMENT TREE FOR EVERY 4" OF EXISTING TREE TO BE REMOVED 184" OF TREE REMOVAL = 16 REPLACEMENT TREES AT 3" CALIPER.

QUANTITY	SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE	
4	BGT	NYSSA SYLVATICA	BLACK GUM TUPELO	3" MIN CALIPER	
4	VGK	ZELKOVA SERRATA 'VILLAGE GREEN'	VILLAGE GREEN ZELKOVA	3" MIN CALIPER	
4	SP	FLOWERING DOGWOOD	SELDOM PINK	3" MIN CALIPER	
4	LW	FLOWERING DOGWOOD	LARGE WHITE	3" MIN CALIPER	

STREET TREES TABULATION. CODE OF THE TOWNSHIP OF HAVERFORD CHAPTER 170 SECTION 2.H.: FOR EVERY 30' OF STREET FRONTAGE THERE WILL BE 1 STREET TREE PLACED. THERE IS 170' OF STREET FRONTAGE = 6 STREET TREES REQUIRED. STREET TREES SHALL BE PLANTED 10' BEHIND R.O.W. LINE.

DUE TO QUANTITY OF REPLACEMENT TREES AND STREET TREES REQUIRED (22) AND LIMITED AREA TO REPLACE TREES BECAUSE OF VEGETATION THE APPLICANT REQUEST A WAIVER.

### GRADING AND CONSTRUCTION NOTES: 1. PROPOSED TEMPORARY TOPSOIL STOCKPILE LOCATION CAN BE PLACED TO THE FRONT OF THE PROPERTY

SAN. M.H. #3 RIM=284.93

13,750 S.F.

TREE PROTECTION-

1. PLANT STANDARDS: ALL SIZES AND GRADING STANDARDS FOR PLANT MATERIALS SHALL CONFORM WITH THE LATEST EDITION OF AMERICAN STANDARD OF NURSERY STOCK AS SPONSORED BY THE

NATIONAL STANDARDS INSTITUTE, INC. OR THE LATEST REVISED EDITION OF THIS STANDARD. 2. PLANT GUARANTY: ALL PLANTING AND RELATED WORK SHALL BE GUARANTEED FOR A PERIOD OF

AMERICAN ASSOCIATION OF NURSERYMEN, INC. AND APPROVED MAY 2, 1986, BY THE AMERICAN

ONE (1) YEAR FROM DATE OF ACCEPTANCE BY THE TOWNSHIP. DEAD PLANT SHALL BE REMOVED IMMEDIATELY AND REPLACEMENT MADE NO LATER THAN DURING THE NEXT PLANTING SEASON.

285.00

MV. IN SW=275.33

INV. IN= 275.33

(SEE DETAIL)

LANUS IN, L STEPHEN & MAUREEN

229 WALNUT HILL LN

FOLIO NUMBER: 22-09-02563-00

PROP. 18" HDPE DEBRIS TRAP

PLACE 6" PVCP @ G=0.50% MIN.

PERF. IN BASIN

BOTTOM: 276.50

/NV.=253.91 8" ∅ (out)

PROP. BASIN 20'X30'X60"-

PLACE 8 LF 8" PERF. PVCP @ G= 0.50%

PROP. 24" CATCH BASIN

INV. IN NW: 254.92 INV. IN N: 254.87

PLANTING NOTES:

PLACE 17 LF 8 PERF. PVCP @ G= 0.50% -

T.G.: 284.05

INV.: 282.25 BOTTOM: 276.50

CONNECT LATERAL— TO EX. SANITARY

SEWER LINE

- AND/OR THE MATERIAL MAY BE TAKEN OFF-SITE TO AN APPROVED LOCATION. 2. THE PROPOSED RESIDENCE SHALL BE PROVIDED WITH A PERMANENT SUBSURFACE DRAINAGE SYSTEM CONSISTING OF PERIMETER DRAINS AND UNDERDRAINS.
- 3. PORTION OF EXISTING SANITARY SEWER IS TO BE PLUGGED WITH CONCRETE AND ABANDONED.
- 4. THE EXISTING SANITARY SEWER EASEMENT IS TO BE EXTINGUISHED.



-PLACE 91 L.F. 8" SDR-26 PVCP @ G=7.13%

INV. IN NE=282.2

(SEE DETAIL)

7,500 S.F.

0.1722 AC.


INV. OUT= 281.82

ANTHONY W & LIŚA YACOVELLI


215 WALNUT HILL LN

FOLIO NUMBER: 22-09-02561-00

- APPROX. LOCATION



ENERAL NOTES: SITE AREA: 21,250 S.F. = 0.4878 AC. SITE IS ZONED R-5 RESIDENTIAL. REQUIREMENTS: LOT SIZE: 5,500 S.F. (MIN.) STREET FRONTAGE: 38 FT. (MIN.) LOT WIDTH AT BUILDING LINE: 50 FT. (MIN.) BUILDING COVERAGE: 30% (MAX.) FRONT YARD: 30 FT. (MIN.) SIDE YARDS: 8 FT. (MIN. EACH); 16 FT. (MIN. AGGREGATE) REAR YARD: 25 FT. (MIN.) BUILDING HEIGHT: 35 FT. (MAX.) IMPERVIOUS SURFACE RATIO: 45% (MAX.) SITE IS NOT LOCATED IN FLOOD HAZARD AREA.



GRADING AND IMPROVEMENTS PLAN TERRADOR PENN LLC. SCALE 1"= 20'

217 WALNUT HILL LN.

HAVERFORD TOWNSHIP SCALE: 1" = 20'

SEPTEMBER 21, 2018

DELAWARE COUNTY, PA

DATE


HERBERT E. MacCOMBIE, JR., P.E. CONSULTING ENGINEERS AND SURVEYORS, INC. P.O. BOX 118

SITE LEGEND

December 27, 2018 1:30 PM

BROOMALL, PA. 19008 SHEET 2 OF 8

CADD FILE GR1\_Walnut\_Hill\_Ln.dwg



### CONSTRUCTION SEQUENCE:

- . PLACE AND PROPERLY SECURE SILT BARRIER FENCE AT THE LOCATIONS SHOWN ON PLAN. CHECK SILT BARRIER FENCE WEEKLY AND AFTER EACH RUNOFF EVENT FOR SERVICEABILITY. REPAIR OR REPLACE ANY DAMAGED SECTIONS AS REQUIRED. . PLACE STONE TIRE CLEANING STRIP AT PROPOSED DRIVEWAY ACCESS FOR FULL WIDTH OF
- DRIVEWAY TO ACT AS A SEDIMENT FILTER TRAP FOR TRUCK EGRESS. USE AASHTO #1 STONE 12"
- STRIP TOP SOIL AND STOCKPILE AT THE LOCATION SHOWN ON THE PLAN, FOR FUTURE USE. PLACE SILT FENCE AROUND TOP SOIL STOCKPILE. I. EXCAVATE FOR PROPOSED BUILDING FOOTINGS. STOCKPILE EXCAVATED GENERAL SOIL MATERIAL TO
- THE FRONT OF THE PROPOSED BUILDING. . CONSTRUCT FOOTINGS AND FOUNDATION WALLS TO THE PROPER ELEVATIONS AND BACKFILL AROUND WALLS TO FINAL GRADE. REMOVE ANY EXCESS EXCAVATED MATERIAL FROM SITE.
- CONSTRUCT PROPOSED STORMWATER MANAGEMENT FACILITIES AT THE LOCATION AND GRADE SHOWN ON PLAN. TAP ROOF DRAINS AS NOTED DIRECTLY INTO THE SPREAD BASIN OR CATCH BASIN. PROVIDE "T" SECTIONS AT DOWNSPOUTS TO PROVIDE FOR OVERFLOW RELIEF TO DISCHARGE ONTO CONCRETE SPLASH PADS. NEWLY CONSTRUCTED INLETS OR CATCH BASINS SHALL BE
- PROTECTED IN ACCORDANCE WITH DETAIL ON PLAN. ALL EXCESS EXCAVATED GENERAL SOIL IS TO BE REMOVED FROM SITE TO AN APPROVED
- 10. CONSTRUCT PROPOSED UTILITY TIE-INS. PLACE DRIVEWAY STONE BASE AND ROUGH GRADE. 1. PAVE PROPOSED DRIVEWAY AND STABILIZE ALL EXPOSED AREAS WITH SOD AND/OR SEEDING AND
- SOIL SUPPLEMENTS, FORMULA B. PROTECT SEEDED AREAS WITH HAY OR MULCH COVERING. 12. TEMPORARY SEEDING IS TO BE APPLIED TO ALL AREAS WHICH WILL REMAIN OPEN FOR LONGER THAN 20 DAYS PRIOR TO PERMANENT GRADING AND SEEDING OR SODDING. USE FORMULA E
- SEEDING AND SOIL SUPPLEMENTS. 13. REMOVE SILT BARRIER FENCE AND INLET/CATCH BASIN PROTECTION ONLY AFTER ALL EXPOSED AREAS HAVE BEEN STABILIZED.

#### SEDIMENTATION AND EROSION CONTROL MEASURES

- SHOULD UNFORESEEN EROSIVE CONDITIONS DEVELOP DURING CONSTRUCTION, THE CONTRACTOR SHALL TAKE ACTION TO REMEDY SUCH CONDITIONS AND TO PREVENT DAMAGE TO ADJACENT PROPERTIES AS A RESULT OF INCREASED RUNOFF AND/OR SEDIMENT DISPLACEMENT. STOCKPILES OF WOOD CHIPS, HAY BALES, CRUSHED STONE AND OTHER MULCHES SHALL BE HELD IN READINESS TO DEAL IMMEDIATELY WITH EMERGENCY PROBLEMS OF EROSION.
- THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF APPENDIX 64, EROSION CONTROL RULES AND REGULATIONS, TITLE 25, PART 1, DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUB-PART C, PROTECTION OF NATURAL RESOURCES, ARTICLE III, WATER RESOURCES, CHAPTER 102. FROSION CONTROL. . A COPY OF THIS EROSION AND SEDIMENTATION CONTROL PLAN MUST BE POSTED AT
- THE CONSTRUCTION SITE IN ACCORDANCE WITH STATE LAW. EROSION CONTROL BLANKET & FORMULA B SEEDING SHALL BE PLACED IN SWALES, DIVERSIONS AND CHANNELS OF CONVEYANCE WHICH WILL BE RECEIVING WATER
- IMMEDIATELY AFTER CONSTRUCTION. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL
- UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENTATION CONTROLS MUST BE MAINTAINED PROPERLY, MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION CONTROLS AFTER EACH STORM EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND RENETTING MUST BE PERFORMED IMMEDIATELY.
- THE DEVELOPER WILL BE RESPONSIBLE FOR THE PROPER CONSTRUCTION. STABILIZATION, AND MAINTENANCE OF ALL EROSION AND SEDIMENTATION CONTROLS AND RELATED ITEMS INCLUDED WITHIN THIS PLAN.
- SHOULD ANY MEASURES CONTAINED WITHIN THIS PLAN PROVE INCAPABLE OF ADEQUATELY REMOVING SEDIMENT FROM ON-SITE FLOWS PRIOR TO DISCHARGE OR OF STABILIZING THE SURFACES INVOLVED, ADDITIONAL MEASURES MUST BE IMMEDIATELY IMPLEMENTED BY THE DEVELOPER TO ELIMINATE ALL SUCH PROBLEMS.

### OPERATION AND MAINTENANCE PROCEDURES

THE FOLLOWING MEASURES SHOULD BE CHECKED AND/OR PERFORMED ON A QUARTERLY BASIS BY THE PROPERTY OWNER:

- 1. IT SHALL BE THE RESPONSIBILITY OF EACH INDIVIDUAL PROPERTY OWNER TO MAINTAIN ANY STORMWATER MANAGEMENT FACILITIES LOCATED ON HIS/HER RESPECTIVE LOT INCLUDING, BUT NOT LIMITED TO, CATCH BASINS, INLETS, INFILTRATION BASINS, DIVERSION CHANNELS, COLLECTION CHANNELS, ROOF DRAINS, STORM SEWERS, CLEAN-OUTS AND SUMPS.
- 2. CATCH BASINS SHOULD BE CLEANED ON A QUARTERLY BASIS OF ANY ACCUMULATED DEBRIS AND SEDIMENT. INFLOW AND OUTFLOW POINTS INTO THE INDIVIDUAL ON-LOT SYSTEMS SHOULD BE KEPT CLEAR OF LEAVES AND OTHER DEBRIS. ANY LEAVES OR DEBRIS WILL NEGATIVELY IMPACT THE PERFORMANCE OF THESE SYSTEMS.
- 3. ROOF DRAINS SHOULD BE CLEANED SEASONALLY.
- 4. ALL DIVERSION CHANNELS AND COLLECTION CHANNELS SHOULD BE MAINTAINED AT ALL TIMES WITH A GOOD STAND OF VEGETATION AND NOT ALTERED BY THE PROPERTY OWNER.
- POST CONSTRUCTION STORMWATER BMP OPERATION AND MAINTENANCE PROCEDURES
- THE FOLLOWING BMPS SHOULD BE CHECKED AS INDICATED BELOW BY THE RESPONSIBLE PARTY INDICATED IN OPERATION AND MAINTENANCE AGREEMENT REVIEWED AND APPROVED BY THE

**GRASS SWALES** 

GRASS SWALES/CHANNELS SHALL BE MAINTAINED WITH GRASS. THE SWALES SHALL BE MOWED AT 2 1/2" TO 3" HIGH. GRASS SWALES SHALL BE WEEDED TO REMOVE INVASIVES. TRASH AND DEBRIS SHALL BE REMOVED FROM THE SWALES IMMEDIATELY. IF EROSION OCCURS UPHILL OF THE SWALE, ANY SEDIMENT DEPOSITED IN THE SWALE SHALL BE REMOVED IMMEDIATELY. THE ERODED AREAS SHOULD BE REPAIRED AND STABILIZED WITH SEED AND MULCH. APPLY SEED AND MULCH TO DISTURBED AREAS OF THE SWALES AFTER SEDIMENT IS REMOVED. GRASS SWALES SHALL BE MAINTAINED BY THE RESPONSIBLE PARTY INDICATED IN THE OPERATION AND MAINTENANCE AGREEMENT REVIEWED AND APPROVED BY THE TOWNSHIP.

### UNDERGROUND INFILTRATION BASINS

INFILTRATION BASINS, INLET GRATES, AND THE SUMP IN THE UPSTREAM INLET SHALL BE INSPECTED QUARTERLY AND AFTER EACH MAJOR STORM. LEAVES AND OTHER DEBRIS SHALL BE REMOVED IMMEDIATELY. CHECK THE UPSTREAM AND DOWNSTREAM STORM SEWER STRUCTURES FOR SEDIMENT ACCUMULATION OR STANDING WATER. CLEAN THE SEDIMENT FROM THE BOTTOM OF THE STRUCTURES AND DISPOSE OF IN AN APPROVED MANNER. INSPECTIONS, OPERATION, MAINTENANCE, AND REPAIRS TO THE UNDERGROUND INFILTRATION BASIN SHALL BE THE RESPONSIBILITY OF THE OWNER AND APPROVED BY THE TOWNSHIP.

### CATCH BASINS


CATCH BASINS, INLET GRATES AND THE SUMP IN THE UPSTREAM INLET SHALL BE INSPECTED QUARTERLY AND AFTER EACH MAJOR STORM. LEAVES AND OTHER DEBRIS SHALL BE REMOVED IMMEDIATELY. CLEAN THE SEDIMENT FROM THE BOTTOM OF THE STRUCTURES AND DISPOSE OF IN AN APPROVED MANNER.

### PLANTING NOTES:

- PLANT STANDARDS: ALL SIZES AND GRADING STANDARDS FOR PLANT MATERIALS SHALL CONFORM WITH THE LATEST EDITION OF AMERICAN STANDARD OF NURSERY STOCK AS SPONSORED BY THE AMERICAN ASSOCIATION OF NURSERYMEN, INC. AND APPROVED MAY 2, 1986, BY THE AMERICAN NATIONAL STANDARDS INSTITUTE, INC. OR THE LATEST REVISED EDITION OF THIS STANDARD.
- PLANT GUARANTY: ALL PLANTING AND RELATED WORK SHALL BE GUARANTEED FOR A PERIOD OF ONE (1) YEAR FROM DATE OF ACCEPTANCE BY THE TOWNSHIP. DEAD PLANT SHALL BE REMOVED IMMEDIATELY AND REPLACEMENT MADE NO LATER THAN DURING THE NEXT PLANTING SEASON.

### GRADING AND CONSTRUCTION NOTES:

- 1. PROPOSED TEMPORARY TOPSOIL STOCKPILE LOCATION CAN BE PLACED TO THE FRONT OF THE PROPERTY AND/OR THE MATERIAL MAY BE TAKEN OFF-SITE TO AN APPROVED LOCATION.
- 2. THE PROPOSED RESIDENCE SHALL BE PROVIDED WITH A PERMANENT SUBSURFACE DRAINAGE SYSTEM
- 3. PORTION OF EXISTING SANITARY SEWER IS TO BE PLUGGED WITH CONCRETE AND ABANDONED.
- 4. THE EXISTING SANITARY SEWER EASEMENT IS TO BE EXTINGUISHED.



EXCAVATION, TRENCHING, AND SHORING

<u>ENERAL NOTES:</u>

ALL EXCAVATIONS, TRENCHING, AND SHORING OPERATIONS SHALL COMPL WITH THE REQUIREMENTS OF ALL UNITED STATES DEPARTMENT OF LABO OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) PUBLICATION OR THE LATEST REVISIONS. SITE AREA: 21,250 S.F. = 0.4878 AC. SITE IS ZONED R-5 RESIDENTIAL.

REQUIREMENTS:

HAVERFORD TOWNSHIP


SCALE: 1" = 20'

HERBERT E. MacCOMBIE, JR., P.E. CONSULTING ENGINEERS AND SURVEYORS, INC. P.O. BOX 118

> BROOMALL, PA. 19008 SHEET 4 OF 8 HAVERFORD FILE #586 CADD FILE ES1\_Walnut\_Hill\_Ln.dwg

SEPTEMBER 21, 2018

December 27, 2018 1:31 PM



NUMBER	TREE	DESCRIPTION / HEALTH	DIAMETER (INCH)	TO BE REMOVED	INSIDE TREE PROTECTED ZONE	TO BE REPLACED
[1]	HEMLOCK		14			
[2]	HEMLOCK		8			
[3]	HEMLOCK	TWIN	4-6			
[4]	HEMLOCK		4			
[5]	HEMLOCK	TWIN	4-4			
[6]	HEMLOCK	TRI	2-2-6			
[7]	HEMLOCK	TWIN	4-4			
[8]	HEMLOCK	TWIN	6-6			
[9]	HEMLOCK	TWIN	4-6			
[10]	HEMLOCK		8			
[11]	HEMLOCK	TWIN	2-2			
[12]	HEMLOCK		10			
[13]	HEMLOCK		8			
[14]	HEMLOCK		8			
[15]	HEMLOCK		8			
[16]	HEMLOCK	TWIN	4-4	Yes		
[17]	HEMLOCK	TWIN	2-4	Yes	Yes	
[18]	HEMLOCK	TWIN	4-6	Yes	Yes	Yes
[19]	HEMLOCK	TWIN	4-6	Yes	Yes	Yes
[20]	HEMLOCK	TWIN	4-6	Yes		
[21]	HEMLOCK	TWIN	4-6	Yes		
[22]	HEMLOCK	TWIN	6	Yes		
[23]	HEMLOCK		4	Yes		
[24]	HEMLOCK	TWIN	4-6			
[25]	HEMLOCK		4			
[26]	HEMLOCK		8			
[27]	HEMLOCK	TWIN	2-4			
[28]	HEMLOCK		6			
[29]	HEMLOCK		6-8			
[30]	HEMLOCK	QUAD	4-4-4-4			
[31]	HEMLOCK		4			
[32]	HEMLOCK	TWIN	4-6			
[33]	HEMLOCK		8			
[34]	HEMLOCK		4			
[35]	HEMLOCK		4			
[36]	HEMLOCK		6			
[37]	HEMLOCK		8			
[38]	HEMLOCK	TWIN	4-6			
[39]	HEMLOCK		10			
[40]	ENGLISH WALNUT		30			
[41]	ENGLISH WALNUT		36	Yes	Yes	Yes
[42]	WHITE OAK		54			
[43]	SPRUCE		12	Yes	Yes	Yes
[44]	WALNUT		14			
[45]	LOCUST		24			
[46]	POPLAR		24			
[47]	NORWAY MAPLE		14			
[48]	WHITE OAK		30			
[49]	LOCUST		44	Yes	Yes	Yes
[50]	LOCUST		34	Yes	Yes	Yes
[51]	ASH		20	Yes	Yes	Yes
[52]	WALNUT		40		Yes	
[53]	DOGWOOD		12			
[54]	WALNUT		20			
[55]	CHERRY		12-14		Yes	
[56]	OAK		36			
[57]	HOLLY		12			
[58]	WALNUT		18			
[59]	WALNUT		14			

### TREE REPLACEMENT TABULATION:

COMPENSATORY PLANTING TABULATION. CODE OF THE TOWNSHIP OF HAVERFORD CHAPTER 170 SECTION 8.A.(1):

1" OF REPLACEMENT TREE FOR EVERY 4" OF EXISTING TREE TO BE REMOVED

184" OF TREE REMOVAL = 16 REPLACEMENT TREES AT 3" CALIPER.

QUANTITY	SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE
4	BGT	NYSSA SYLVATICA	BLACK GUM TUPELO	3" MIN CALIPER
4	VGK	ZELKOVA SERRATA 'VILLAGE GREEN'	VILLAGE GREEN ZELKOVA	3" MIN CALIPER
4	SP	FLOWERING DOGWOOD	SELDOM PINK	3" MIN CALIPER
4	LW	FLOWERING DOGWOOD	LARGE WHITE	3" MIN CALIPER


STREET TREES TABULATION. CODE OF THE TOWNSHIP OF HAVERFORD CHAPTER 170 SECTION 2.H.: FOR EVERY 30' OF STREET FRONTAGE THERE WILL BE 1 STREET TREE PLACED. THERE IS 170' OF STREET FRONTAGE = 6 STREET TREES REQUIRED.


STREET TREES SHALL BE PLANTED 10' BEHIND R.O.W. LINE.

DUE TO QUANTITY OF REPLACEMENT TREES AND STREET TREES REQUIRED (22) AND LIMITED AREA TO REPLACE TREES BECAUSE OF VEGETATION THE APPLICANT REQUEST A WAIVER.

### PLANTING NOTES:


- 1. PLANT STANDARDS: ALL SIZES AND GRADING STANDARDS FOR PLANT MATERIALS SHALL CONFORM WITH THE LATEST EDITION OF AMERICAN STANDARD OF NURSERY STOCK AS SPONSORED BY THE AMERICAN ASSOCIATION OF NURSERYMEN, INC. AND APPROVED MAY 2, 1986, BY THE AMERICAN NATIONAL STANDARDS INSTITUTE, INC. OR THE LATEST REVISED EDITION OF THIS STANDARD.
- 2. PLANT GUARANTY: ALL PLANTING AND RELATED WORK SHALL BE GUARANTEED FOR A PERIOD OF ONE (1) YEAR FROM DATE OF ACCEPTANCE BY THE TOWNSHIP. DEAD PLANT SHALL BE REMOVED IMMEDIATELY AND REPLACEMENT MADE NO LATER THAN DURING THE NEXT PLANTING SEASON.






December 27, 2018 1:31 PM

CADD FILE DT1\_Walnut\_Hill\_Ln.dwg





THE MEETING OF THE PLANNING COMMISION OF HAVERFORD TOWNSHIP, THURSDAY, JANUARY 24, 2019 AT 7:00 P.M. IN THE COMMISSIONERS MEETING ROOM, 1014 DARBY ROAD, HAVERTOWN, PA 19083

#### **BOARD MEMBERS PRESENT:**

Angelo Capuzzi, Chairman

Chuck Reardon, Vice Chairman

Robert Fiordimondo, member

Jesse Pointon, member

Joseph Russo, Member

#### **BOARD MEMBERS NOT PRESENT:**

Paul D'Emilio, member

Christian Guamann, Secretary

#### ALSO PRESENT:

Kelly Kirk, Planning and Zoning Officer

Chuck Faulkner, Pennoni Assoc.

Lisa Favacchia, Recording Secretary

#### Item #1 REORGANIZATION/APPOINTMENTS

A. Motions approved to elect the following candidates to their respective positions:

(1) Chairman Angelo Capuzzi

(2) Vice- Chairman Chuck Reardon

(3) Secretary Christian Guamann

B. Motion approved to appoint Lisa Favacchia as scribe for the year 2019.

C. Motion to set the following 2019 calendar of meetings for the Planning Commission:

January 24<sup>th</sup>

July 25<sup>™</sup>

February 14 & 28

August 22<sup>™</sup>

March 14 & 28

September 12 & 26

April 11 & 25

October 10 \* & 24 \*

May 9<sup>th</sup> & 23<sup>th</sup>

November 14<sup>th</sup>

June 13<sup>™</sup> & 27<sup>™</sup>

December 12<sup>h</sup>

Meetings shall convene at 7:30 P.M.

MOTION PASSED

### Item #2 Preliminary/Final Land Development Plan

1400 Lawrence Road- Lynnewood Elementary School

School District of Haverford Township

The applicant, The School District of Haverford Township, proposes to construct a new school, athletic field, parking areas, and playgrounds, and then demolish the existing Lynnewood Elementary School. The property is located in the INS Institutional Zoning District.

Thomas Hanna of Gilmore & Associates, the civil engineer for the Haverford Township School District, addresses the Board. Since the last meeting with the Board, the School District has prepared several revisions to their plans of the new school.

The revised Township Engineer review letter dated January 24, 2019 was reviewed with the Board. The applicant indicated that they would comply with the outstanding issues raised by the Township Engineer.

The items questioned by the Board included the status of the approval for the Zoning variances, the depiction and future use of the open space areas outlined on the plan, construction of a new baseball field on Township property, location of contractors

staging areas, phasing of construction and potential impacts to the existing school's sanitary sewer service during construction of the proposed detention basin.

Mr. Capuzzi makes a motion to recommend to the Board of Commissioners that the preliminary/final land development plans for the Lynnewood Elementary School be approved, subject to the following conditions:

- 1. The Zoning Board decision and a listing of the variances granted shall be listed on the Record Plan.
- 2. The limits of the proposed open space areas shall be depicted on the Record Plan.
- 3. A handicap accessible curb cut ramp be constructed on the south side of Lawrence Road at the existing cross walk.
- 4. Missing dimensions from the title line in Lawrence Road and the location of proposed property marker monuments be added to the Record Plan.
- 5. The limits of the easement for the proposed 5-foot wide sidewalk along Lawrence Road shall be added to the Title Plan, as well as a notation regarding the School District's responsibility to own and maintain this walkway.
- 6. Details for the construction of the new baseball field on Township property shall be prepared by the School District to the satisfaction of the Township, and that the new ball file be constructed by the School District.
- 7. All outstanding comments in the Township engineer's review letter of January 24, 2019 be addressed to the satisfaction of the Township.
- 8. The six waivers requested by the Applicant be approved by the Board of Commissioners.

Mr. Pointon seconds the motion

Lisa Favacchia calls roll

MOTION PASSED (5 - 0)

### Item #3 Preliminary/Final Minor Subdivision Plan

1200 Ellston Road

Ormond Properties, LLC

The applicant, GMG Holdings LLC, proposes to subdivide an existing 15,878 s.f. parcel (Folio no. 22-09-00730-00) into two (2) lots. Lot 1 is proposed to be 9,723 s.f. and Lot 2 is proposed to be 6,154 s.f. The existing dwelling and associated walkways on Lot 1 are proposed to remain and a new single-family dwelling is proposed for Lot 2. additionally, four (4) new parking spaces are proposed for Lot 1. A seepage bed is proposed on each lot for stormwater management. The property is located within the R-4 Low to Medium Density Residential Zoning District.

Michael Ciocco of Catania Engineering Associates, the civil engineer for the project, addressed the Board and provided a general description of the proposed development as well as a brief history of the site in regards to previous zoning decisions related to the property. Mr. Ciocco addressed the comments contained in the Township Engineer's revised review letter dated January 24, 2019 and indicated that it was the Applicant's intent to comply with all of the comments.

Some of the items discussed with the Board included proposed variance request for street right-of-way, sidewalks and street lighting, the size of the new lot, setbacks and the proposed building footprint, sidewalks and foot traffic within the immediate neighborhood, and the limitation to two (2) rental units in the existing building on the property.

Linda Eberle of 12055 Center Avenue asks if the property will continue to be rented out with two single family units. She also asks if safety fencing will be installed around the basement excavation and expresses concerns about possible subsurface water conditions and stormwater runoff impacts to her property.

The next neighbor to ask questions is Bryan Ramona from 14 N. Belleview Ave. He asks if the property is zoned properly to be considered a multi-family residence. Mr. Ramona expresses concerns about additional traffic created by the development, current problems related to on-street parking and speeding vehicles. He also asks about any proposed improvements to the existing building on the property.

Nick Caramanico from 108 Peach Lane has a question concerning the approval process for the subdivision.

Mark McCarty from 1209 Ellston Road expresses his concerns about the stormwater runoff from the development, potential issues regarding back-up of sanitary sewage flows and the prior removal of exi9sting trees from the property.

The Board deferred action on this plan at this time and requested that revised plans addressing the Township Engineer's review comments and providing justifications for any waivers being requested be submitted for review and approval.

### Item #4 Preliminary/Final Minor Subdivision Plan

1417 Fairview Road

Ormond Properties, LLC

The applicant, Ormond Properties LLC, proposes to subdivide an existing 42,000 s.f. parcel (Folio no. 22-09-00877-00) into two (2) lots. Lot 1 is proposed to be 25,500 s.f. and Lot 2 is proposed to be 16,500 s.f. The existing dwelling, garage and driveway are proposed to be demolished and a new single-family dwelling on each lot is proposed. A seepage bed is proposed on each lot for stormwater management. The property is located within the R-4 Low to Medium Density Residential Zoning District. The proposed

lots will be serviced by public water and sewage facilities, both of which are available in Fairview Avenue.

Michael Ciocco of Catania Engineering Associates, the civil engineer for the project, addressed the Board and provided a general description of the proposed development and confirmed the existence of steep (15% to 25%) slopes on the property. Mr. Ciocco addressed the comments contained in the Township Engineer's revised review letter dated January 21, 2019 and indicated that it was the Applicant's intent to comply with all of the comments.

The applicant has requested a waiver from the two-step plan review process and to allow the plan to be considered as a preliminary/final plan.

Some of the items discussed by the Board include street lighting, existing bituminous curbing, removal of additional trees during construction, placement of proposed sewer and water service laterals, and the potential impact on remaining steep slopes created by future improvements on the proposed lots.

Nick DiTrolio, 1420 Parkside Drive, asked that any diseased/dead tree at the rear of the property be removed so that they do not impact his adjacent property.

Don Bonhage, 1432 Parkside Drive, expressed concerns about impacts to the safety of pedestrian traffic on Fairview Avenue related to the absence of sidewalks, the narrowness of the existing cartway and on-street parking.

Raelyn Harman, 1413 Fairview Avenue, also expressed concerns about on-street parking and the steep grade on Fairview Avenue. Ms. Harman also expressed concerns about impacts to her property from landscaping on adjacent properties.

The Board deferred action on this plan at this time and requested that revised plans addressing the Township Engineer's review comments and providing justifications for any waivers being requested be submitted for review and approval.

### Item #5 Preliminary/Final Minor Subdivision Plan

217 Walnut Hill Lane

Terrador Properties, LLC

The applicant, Terrador Penn LLC, proposes to subdivide an existing 21,250 s.f. parcel (Folio no. 22-09-02562-00) into two (2) lots. Lot 1 is proposed to be 7,500 s.f. and Lot 2 is proposed to be 13,750 s.f. The existing dwelling and driveway are proposed for Lot 2. A seepage bed is proposed on Lot 2 for stormwater management. The property is located within the R-5 Low to Medium Density Residential Zoning District.

The applicant has requested waivers for the minimum right-of-way width of 50 feet and cartway width of 27 feet for Walnut Hill Lane if required. The existing right-of-way and cartway widths are 48 feet and 24 feet. Another waiver will be regarding the two-step review process. Another waiver regarding the street tree and replacement tree requirements will be requested. The Applicant indicates that he will work with the Shade Tree Commission to determine how best to provide landscaping for the project.

Dennis O'Neill of H. E. MacCombie Jr. Engineering, the civil engineer for the project, addressed the Board and provided a general description of the proposed development and confirmed the existence of steep (15% to 25%) and very steep (greater than 25%) slopes on the property. Mr. O'Neill addressed the comments contained in the Township Engineer's revised review letter dated January 21, 2019 and indicated that it was the Applicant's intent to comply with all of the comments.

Some items discussed by the Board include the potential impact on remaining steep slopes created by future improvements on the proposed lots, the need for limit-of-disturbance fencing to control the extent of steep slope disturbance during construction, the limits of the tree protection zone and the impact to the driveway apron and sidewalk on the property across the street as related to the sanitary sewer relocation.

Len Orsini, 220 Walnut Hill Lane, asked about the details of the sanitary sewer reconstruction and its impact to his driveway and sidewalk (Mr. Orsini lives across the street from the subdivision).

Mr. Capuzzi makes a motion to recommend approval of the preliminary/final subdivision plan for 217 Walnut Hill Lane to the Board of Commissioners subject to the following conditions:

- 9. That all outstanding comments in the Township engineer's review letter of January 21, 2019 be addressed to the satisfaction of the Township.
- 10. That the side yard setback on the west side of Lot 1 be increased to 8.8 feet.

Mr. Reardon seconds the motion

Lisa Favacchia calls roll

MOTION PASSED (5-0)

Mr. Reardon makes a motion to adjourn the meeting.

Mr. Capuzzi seconds the motion.

Motion approved by a verbal vote of 5 - 0.

MEETING ADJOURNED AT 9:05 P.M.

angelo M. Capuzzo 6/13/19

#### AGENDA

THE MEETING OF THE PLANNING COMMISSION OF HAVERFORD TOWNSHIP, THURSDAY, FEBRUARY 14, 2019 AT 7:30 P.M. IN THE COMMISSIONERS MEETING ROOM, HAVERFORD TOWNSHIP MUNICIPAL SERVICES BUILDING, 1014 DARBY ROAD, HAVERTOWN, PA 19083

#### BOARD MEMBERS:

Angelo Capuzzi, Chairman Chuck Reardon, Vice Chairman Christian Gaumann, Secretary Paul D'Emilio Robert Fiordimondo Jesse Pointon Joseph Russo

#### ALSO PRESENT:

Chuck Faulkner, Pennoni Assoc. Kelly Kirk, Planning & Zoning Officer Lisa Favacchia, Recording Secretary

Item #1 Final Land Development Plan

924 Haverford Road

Pets First Veterinary Center LLC

Item #2 Preliminary/Final Land Development Plan

2400 Darby Road Republic Bank

Item #3 Review of Minutes

**ADJOURNMENT** 

#### AGENDA

THE MEETING OF THE PLANNING COMMISSION OF HAVERFORD TOWNSHIP, THURSDAY, FEBRUARY 28, 2019 AT 7:30 P.M. IN THE COMMISSIONERS MEETING ROOM, HAVERFORD TOWNSHIP MUNICIPAL SERVICES BUILDING, 1014 DARBY ROAD, HAVERTOWN, PA 19083

#### **BOARD MEMBERS:**

Angelo Capuzzi, Chairman Chuck Reardon, Vice Chairman Christian Gaumann, Secretary Paul D'Emilio Robert Fiordimondo Jesse Pointon Joseph Russo

#### ALSO PRESENT:

Chuck Faulkner, Pennoni Assoc. Kelly Kirk, Planning & Zoning Officer Lisa Favacchia, Recording Secretary

Item #1 Preliminary/Final Minor Subdivision Plan

1400 Ellston Road

Ormond Properties, LLC

Item#2- Preliminary/Final Minor Subdivision Plan

1417 Fairview Road Ormond Properties, LLC

Item #3 Preliminary/Final Land Development Plan

2400 Darby Road Republic Bank

Item #4 Review of Minutes

THE MEETING OF THE PLANNING COMMISION OF HAVERFORD TOWNSHIP, THURSDAY, FEBRUARY 28, 2019 AT 7:30 P.M. IN THE COMMISSIONERS MEETING ROOM, 1014 DARBY ROAD, HAVERTOWN, PA 19083

#### **BOARD MEMBERS PRESENT:**

Angelo Capuzzi, Chairman Chuck Reardon, Vice Chairman Christian Guamann, Secretary Robert Fiordimondo, member

Jesse Pointon, member

#### **BOARD MEMBERS NOT PRESENT:**

Paul D'Emilio, member Joseph Russo, Member

#### ALSO PRESENT:

Kelly Kirk, Planning and Zoning Officer

Chuck Faulkner, Pennoni Associates, Township Engineer
Lisa Favacchia, Recording Secretary

Mr. Capuzzi discloses that he Planning Commission met in executive session prior to the regular meeting to receive information relative to a field meeting that was held between representatives of PennDOT, Haverford Township and Republic Bank to discuss the disposition of the proposed right turn lane from southbound Darby Road to westbound Eagle Road.

#### Item #1 Preliminary/Final Minor Subdivision Plan

#### 1400 Ellston Road

#### **Ormond Properties. LLC**

The applicant, GMG Holdings LLC, proposes to subdivide an existing 15,878 sq ft parcel (Folio No. 22-09-00730-00) into two lots. Lot 1 is proposed to be 9,723 sq ft and Lot 2 is proposed to be 6,154 sq ft. The existing dwelling and associated walkways on Lot 1 are proposed to remain and a new single-family dwelling is proposed for Lot 2. Additionally, four new parking spaces are proposed for Lot 1. A seepage bed is proposed on each lot for stormwater management. The property is located within the R-4 Low to Medium Density Residential Zoning District.

The existing dwelling is currently serviced by public water and sanitary sewer. The proposed dwelling on Lot 2 is also to be serviced by public water and sanitary sewer, with new service laterals connecting to existing utilities in Ellston Road.

The applicant has requested approval of the following waivers from the applicable SALDO requirements: (1) the two-step plan review process; (2) to allow a 40-foot right-of-way and a 24.3-foot cartway for Peach Lane and a 40-foot right-of-way and a 23.5-foot cartway for Ellston Road (in lieu of 50-foot right-of-way and 27-foot cartway); (3) installation of sidewalks on Peach Lane and Ellston Road; and (4) installation of street lighting on Peach Lane and Ellston Road.

Michael Ciocco, of Catania Engineering Associates, addresses the Board on behalf of the applicant for the final minor subdivision of 1400 Ellston Road. Mr. Ciocco addressed the comments contained in the Township Engineer's review letter dated February 27, 2019. Mr. Ciocco indicated that the applicant will comply with the remaining issues listed in the Township Engineer's review letter and handed up a red-lined drawing showing how the issues would be satisfied. The major issues addressed included the location of the sanitary sewer lateral for Lot 2 and the location of the proposed seepage beds on the lots and how runoff will be directed towards those beds.

The following items were discussed by the Board with the applicant: required infiltration testing for the revised seepage bed locations; disturbance of the existing parking area on Lot 1 in order to construct the proposed seepage bed on Lot 1; extension of the proposed sanitary sewer main in the public right-of-way to the approximate location of the first proposed clean-out shown on the red-lined drawing; confirmation that Aqua PA will allow the water service lateral for Lot 2 to cross through Lot 1; if there is a buried oil tank on Lot 1, if it is currently in use, and if not, will it be removed; and the need for a profile of the proposed sanitary sewer main and the proposed sewer lateral to Lot 2.

Mr. Capuzzi makes a motion recommending that the Board of Commissioners approve the Preliminary/Final Minor Subdivision Plan for 1400 Eliston Road subject to the following conditions:

- 1. That the comments contained in the Township Engineer's review letter dated February 27, 2019 be addressed to the satisfaction of the Township;
- 2. That the proposed sanitary manhole in Ellston Road be moved to the approximate position of the first clean-out as shown on the red-lined drawing presented to the Board at the meeting:
- 3. That documentation is received from Aqua PA regarding the location of the proposed water service lateral for Lot 2;
- 4. That final revisions to the subdivision plan be reviewed and approved by the Township staff prior to its being submitted to the Board of Commissioners for final action; and
- 5. That an additional clean-out be added to the sanitary lateral run to Lot 2, such that the spacing between any two clean-outs does not exceed 75-feet.

Mr. Guamann seconds this motion.

Lisa Favacchia calls roll.

Motion passes 5-0.

#### Item #2 Preliminary/Final Minor Subdivision Plan

#### 1417 Fairview Road

#### **Ormond Properties, LLC**

The applicant, Ormond Properties LLC, proposes to subdivide an existing 42,000 sq ft parcel (Folio No. 22-09-00877-00) into 2 lots. Lot 1 is proposed to be 25,500 sq ft and Lot 2 is proposed to be 16,500 sq ft. The existing dwelling, garage and driveway are proposed to be demolished and a new single-family dwelling on each lot is proposed. A seepage bed is proposed on each lot for stormwater management. The property is located within the R-4 Low to Medium Density Residential Zoning District.

The existing dwelling is currently serviced by public water and sanitary sewer. The proposed dwellings are to be serviced by public water and sanitary sewer, with new service laterals connecting to existing utilities in Fairview Avenue.

The applicant has requested approval of the following waivers from the applicable SALDO requirements: (1) the two-step plan review process; (2) to allow a 21.4-foot cartway for Fairview Avenue in lieu of a 27-foot cartway; (3) installation of sidewalks on Fairview Avenue; (4) installation of street lighting on Fairview Avenue; and (5) to allow the restoration of the existing bituminous curb in lieu of installing new concrete or granite curb.

Michael Ciocco, of Catania Engineering Associates, addresses the Board on behalf of the applicant for the final minor subdivision of 1417 Fairview Avenue. Mr. Ciocco addressed the comments contained in the Township Engineer's review letter dated February 27, 2019. Mr. Ciocco indicated that the applicant will comply with the remaining issues listed in the Township Engineer's review letter.

The following items were discussed by the Board with the applicant: the status of the inspection of trees on the property to determine which dead/diseased trees will be removed; the Delaware County Planning Department's request to photo-document the existing dwelling located on the

property before it is demolished; and the condition of the existing bituminous curb along the property frontage and required repairs to same.

Mr. Capuzzi makes a motion recommending that the Board of Commissioners approve the Preliminary/Final Minor Subdivision Plan for 1417 Fairview Avenue subject to the following conditions:

- 6. Comments contained in the Township Engineer's review letter dated February 27, 2019 be addressed to the satisfaction of the Township;
- 7. the applicant cooperates with and allows the Delaware County Planning Department's to photo-document the existing dwelling on the property; and
- 8. the trees on the property that are dead or diseased trees be removed during construction of the new homes.

Mr. Guamann seconds this motion.

Lisa Favacchia calls roll.

Motion passes 5-0.

#### Item #3 Preliminary/Final Land Development Plan

2400 West Darby Road

#### Republic Bank

The applicant, Republic Bank, proposes to construct a new bank building and associated parking at the referenced property (Folio No. 22-03-00690-00). The existing gas station is proposed to be demolished. An infiltration bed is proposed for stormwater management. The property is located within the C-3 Commercial Zoning District.

The applicant has been granted the following waivers:

From Section 160-4.E(5)[e](4) requiring that all storm drainage, sanitary sewer and public water supply lines or facilities within 400 feet of the site and ownership and maintenance responsibilities of the same to be indicated on the plan.

From Section 160-5.B(6) requiring that shade trees be installed on both sides of all streets subject to the approval of the Shade Tree Commission at a minimum spacing along each side of street of 30 feet on center.

A partial waiver from Section 160-5.B(8) requiring that permanent survey monuments are required at right-of-way lines, at the corners and at angle points. Due to proposed improvements at some locations, an alternative marker is proposed.

Mark Damico, attorney for the applicant addresses the Board and gives a brief history and overview of the project, including meetings and approvals and variances granted by the Township Zoning Hearing Board, including relief for the proposed site signage.

Robert Blue of Robert E. Blue Consulting Engineers, the civil engineer for the project, and Nicole Kline of McMahon Associates, the traffic engineer for the project, address the comments contained in the township Engineer's review letter dated February 12, 2019. The applicant intends to comply with the comments and address them in a revised submission.

Ms. Kline explains the changes made to the plan in regards to the elimination of the previously proposed right turn lane from southbound Darby Road onto westbound Eagle Road. As a result of a field meeting held with representatives of PennDOT, the Township and the applicant, it was determined that, given its relatively short length and limited accessibility, the previously proposed right turn lane would add little to improving vehicle movements through the Darby Road/Eagle Road intersection. Rather, it was PennDOT's opinion that a modification of the curb radius (enlarging to 40-feet) at that corner of the intersection would be a much more worthwhile and effective traffic improvement. Ms. Kline also discussed the possibility of improving (enlarging to 45-feet) the curb radius at the corner across Eagle Road at the Grace Chapel property and the benefits that would be derived for traffic turning from eastbound Eagle Road onto southbound Darby Road. However, to effect this improvement, approximately 80 sq ft of additional right-of-way would be required from the owners of the Grace Chapel property. Ms. Kline further indicated that the proposed driveway connection to Darby Road would be limited to right-turn-in and right-turn-out movements, while the driveway connection to Eagle Road would allow both right and left-turn-in, but only right-turn-out movements.

The following items were discussed by the Board with the applicant: the need for a physical control barrier/island at the Eagle Road driveway to dissuade left turn movements from the site onto eastbound Eagle Road; whether the Zoning Board will need to amend their conditions of approval for the project if the right turn lane is not constructed; into which stage of the approval process does the modified site plan fit; the need to fully comply with the Eagle Road design standards in regards to fencing, piers, street lighting and grass strips between curb and sidewalk; and hours of operation on Friday nights.

Mr. Capuzzi makes a motion recommending that the Board of Commissioners approve the Preliminary Land Development Plan for 2400 West Darby Road (Republic Bank) subject to the following conditions:

- 9. That the applicable comments contained in the Township Engineer's review letter dated February 12, 2019 be addressed to the satisfaction of the Township;
- 10. That the applicable Eagle Road design standards for fencing, piers, street lighting and grass strips adjacent to sidewalks be incorporated into the final plan;
- 11. That the applicant continue to work with PennDOT, the Township and Grace Chapel in designing the proposed intersection improvements along Eagle and Darby roads; and
- 12. That a physical barrier be constructed at the site driveway connection to Eagle Road to help prevent left turn movements from the site on to eastbound Eagle Road.

Mr. Reardon seconds this motion.

Lisa Favacchia calls roll

#### Motion passes 5-0.

- Mr. Capuzzi makes a motion to approve the meeting minutes of November 8, 2018.
- Mr. Reardon seconds this motion.

Motion passes 5-0.

- Mr. Capuzzi makes a motion to adjourn the meeting.
- Mr. Pointon seconds this motion.

Motion passes 5-0.

ADJOURNMENT at 8:40 P.M.

angelo Mr. Capuzió 6/12/19

## **AGENDA**

### Haverford Township Planning Commission Meeting

March 14, 2019 | 7:30 p.m. Haverford Township Municipal Services Building 1014 Darby Road, Havertown, PA 19083

#### Planning Commission Members:

Angelo Capuzzi, Chairman | Chuck Reardon, Vice Chairman | Christian Gaumann, Secretary | Paul D'Emilio | Robert Fiordimondo | Jesse Pointon | Joseph Russo

#### Others in Attendance:

Chuck Faulkner, Pennoni Assoc. | Kelly Kirk, Zoning Officer & Community Planner | Lisa Favacchia, Recording Secretary

#### Agenda Items

- 1. Opening of Meeting
  - a. Roll Call
  - b. Pledge of Allegiance
- 2. 924 Haverford Road, Final Land Development Plan

Pets First Veterinary Center, LLC

3. Review of Minutes

Adjournment

THE MEETING OF THE PLANNING COMMISION OF HAVERFORD TOWNSHIP, THURSDAY, MARCH 14, 2019 AT 7:30 P.M. IN THE COMMISSIONERS MEETING ROOM, 1014 DARBY ROAD, HAVERTOWN, PA 19083

#### **BOARD MEMBERS PRESENT:**

Angelo Capuzzi, Chairman

Chuck Reardon, Vice Chairman

Robert Fiordimondo, Member

Christian Guamann, Secretary

#### **BOARD MEMBERS NOT PRESENT:**

Paul D'Emilio, Member

Joseph Russo, Member

Jesse Pointon, Member

#### ALSO PRESENT:

Kelly Kirk, Planning and Zoning Officer

Chuck Faulkner, Pennoni Associates, Township Engineer

Andy Lewis, Fifth Ward Commissioner

#### Item #1 Opening of Meeting

- a. Roll Call
- b. Pledge of Allegiance

#### Item #2 924 Haverford Road, Final Land Development Plan Pets First Veterinary Center, LLC

The applicant, Pets First Veterinary Center, LLC, proposes to demolish the existing veterinary building and parking area at the referenced property (Folio No. 22-05-00399-00). The existing residential dwelling located on the property is proposed. An underground infiltration bed is proposed for storm water management. The property is in the R-4 Residential Zoning District. The site will be served by public water sanitary sewer

The applicant has been granted the following waivers from the requirements of the Township's Subdivision and Land Development regulations:

1. Depicting the location of existing storm drainage, sanitary sewer and public water supply lines or facilities within 400 feet of the site.

2. Providing a location map or key map showing the location of the site and all property lines, streets, zoning and watercourses within 2,000-feet of the site.

3. Installation of street lighting for a non-residential development.

James Greenfield, the Applicant's attorney, informed the Board that the Board of Commissioners had approved the preliminary land development plan for this project and then introduced Dan Meier, the civil engineer for the project. Mr. Meier discussed the comments contained in the Township Engineer's revised review letter dated March 14, 2019. The applicant has submitted a sewage planning exemption request and has received initial comments from PennDOT regarding their highway occupancy permit application and has revised the plan to address those comments. The design for the lower courtyard is about 90% complete and further details will be provided prior to final approval.

The following comments pertain to the current final plan submission:

- Regarding the installation of sidewalks, the Applicant is now requesting a waiver from the requirement to install sidewalk along the property's frontage on Haverford Road.
- 2. The Applicant will confirm that the depth of the insert proposed for the inlets will not impact or interfere with the proper functioning of the system.

Mr. Silvio DeAngelo, owner of 904, 908 and 912 Haverford Road, his wife, Maura, and their attorney, Fintan McHugh, all spoke against the 6-foot high fence which was recently installed by the Applicant along the common boundary line between Mr. DeAngelo's and that of the Applicant's. It was the Board's opinion that the Applicant has a right to install a fence on its property provided that the fence is installed in accordance with all of the Township's applicable requirements. The Township will send a representative to the site to confirm that the fence confirms with all of the Township standards.

Lynn Elliot, 704 Polo Road, indicated her opposition to the project and felt that it was inappropriate to permit such a large expansion of a non-conforming commercial use in a residential district. Ms. Elliot did confirm that her concerns and objections had been presented to the Zoning Board during their review and deliberations on the project.

Mr. Capuzzi makes a motion to recommend approval to the Board of Commissioners of the Final Land Development for Pets First LLC subject to the following conditions:

- 1. That all outstanding comments contained in the revised Township Engineer's review letter dated March 14, 2019 be addressed to the satisfaction if the Township;
- 2. That the final design of the lower courtyard area be reviewed and approved by the Township before the final land development plans for the project are presented to the Board of Commissioners for final approval; and

3. The waiver request regarding the installation of sidewalks along Haverford Road be denied.

Mr. Guamann seconds the motion

Motion passed 4-0.

#### Item #3 Review of the Minutes

Mr. Capuzzi makes a motion to approve the meeting minutes of December 13, 2018.

Mr. Guamann seconds this motion.

#### Motion passed 4-0

Mr. Capuzzi makes a motion to adjourn the meeting.

Mr. Reardon seconds this motion.

Motion passed 4-0.

ADJOURNMENT at 8:40 P.M.

angelom. Capupi 6/13/19

# **AGENDA**

# Haverford Township Planning Commission Meeting

April 11, 2019 | 7:30 p.m. Haverford Township Municipal Services Building 1014 Darby Road, Havertown, PA 19083

## Planning Commission Members:

Angelo Capuzzi, Chairman | Chuck Reardon, Vice Chairman | Christian Gaumann, Secretary | Paul D'Emilio | Robert Fiordimondo | Jesse Pointon | Joseph Russo

### Others in Attendance:

Chuck Faulkner, Pennoni Assoc. | Kelly Kirk, Zoning Officer & Community Planner | Lisa Favacchia, Recording Secretary

#### Agenda Items

- 1. Opening of Meeting
  - a. Roll Call
  - b. Pledge of Allegiance
- 2. Haverford High School- 200 Mill Road

Land Development Sketch Plan

3. Republic Bank- 2300 Darby Road

Final Land Development Plan

4. Proposed Student Rental- 510 College Avenue

Review for conformance with the Comprehensive Plan per §182-202B(3)

5. Indoor Recreational Facility- 1025 West Chester Pike

Review for conformance with the Comprehensive Plan per §182-404B(3)

6. Review of Minutes

THE MEETING OF THE PLANNING COMMISION OF HAVERFORD TOWNSHIP, THURSDAY, APRIL 11, 2019 AT 7:30 P.M. IN THE COMMISSIONERS MEETING ROOM, 1014 DARBY ROAD, HAVERTOWN, PA 19083

#### **BOARD MEMBERS PRESENT:**

Angelo Capuzzi, Chairman Chuck Reardon, Vice Chairman Robert Fiordimondo, member Jesse Pointon, member

#### **BOARD MEMBERS NOT PRESENT:**

Paul D'Emilio, member Joseph Russo, Member Christian Guamann, Secretary

#### ALSO PRESENT:

Kelly Kirk, Planning and Zoning Officer
Chuck Faulkner, Pennoni Associates, Township Engineer
Lisa Favacchia, Recording Secretary

#### Item #1 Opening of Meeting

- a. Roll Call
- b. Pledge of Allegiance

# Item #2 Haverford High School- 200 Mill Road Land Development Sketch Plan

Tom Hanna from Gilmore & Associates and Casey Orr from KCB Architects approached the Board to present a sketch plan for land development at Haverford High School. The project includes the construction of a 3-story, 15 classroom addition at the northeast corner of the existing high school building and a 1-story addition for the band and orchestra at the northwest corner of the building. Also included in the project will be modifications and expansions to the existing parking facilities on the site. Variances will be required for both impervious coverage and building coverage. From a staging perspective, the 3-story addition will be constructed first, with work starting in December 2020 and running into 2021. The 1-story addition and parking modifications will be completed during the 2021-2022 time period. The Applicant has received a copy of the Township Engineer's review letter dated April 11, 2019 and all comments will be addressed in the plans submitted for land development approval.

Among the items discussed by the Board included access to existing school facilities during construction, future building expansion, expected student enrollment (which is expected to peak at 2300 students), School district policies regarding students parking on campus, proposed interior modifications to the building, required parking spaces on the site, grading for the modifications to the existing parking areas and drainage at the loading dock area.

# Item #3 Republic Bank- 2300 Darby Road Final Land Development Plan

Mark D'Amico, the attorney for Republic Bank, Leon McGuire of Robert E. Blue Consulting Engineers, presented the Final Land Development plan for Republic Bank on 2300 Darby Road. The preliminary plans were approved by the Board of Commissioners and some of the changes made to this final plan include a reduction in the number of parking spaces from 28 to 20, a reduction in the impervious coverage to 80% and the creation of a 4-foot wide grass strip between the curb and sidewalk along the site frontages. The Applicant has received a copy of the Township Engineer's review letter dated April 11, 2019 and will comply with all of the comments contained therein.

Some of the items discussed by the Board included the positioning of required trees on the site, review of the landscape plan by the Shade Tree Commission, contaminated site soils, infiltration testing for the proposed stormwater management facility, curb and sidewalk modifications at the Grace Chapel corner of Eagle and Darby Roads, Eagle Road Corridor improvements and the dedication of additional right-of-way to PennDOT.

Mr. Capuzzi makes a motion to recommend approval of the Final Land Development Plan for Republic Bank to the Board of Commissioners subject to the following conditions:

- 1. All of the outstanding comments contained in the Township Engineer's review letter dated April 11, 2019 shall be addressed to the satisfaction of the Township;
- Republic Bank shall be additionally responsible for the design, permitting and construction of the proposed expanded 45-curb radius improvements at the southwest corner of the Darby/Eagle Roads intersection (i.e., the Grace Chapel corner) subject to the Township obtaining any additional required right-of-way;
- 3. A minimum of four (4) light poles and fixtures meeting the requirements of the Eagle Road Corridor Standards shall be incorporated into the site plan;
- 4. The decorative fencing and support piers shall be extended by an additional total distance of approximately 45-feet to close off the gaps in the fencing along Darby Road and Eagle Road; and
- 5. A note shall be added to the plan which will allow for the adjustment of the western end of the Eagle Road sidewalk should future development occur on the property to the west of this site.

Mr. Pointon seconds the motion

**Motion Passes 4-0** 

# Item #4 Proposed Student Rental- 510 College Avenue Review for conformance with the Comprehensive

Jamie Jun of Fromhold Jaffe & Adams, PC, appeared before the Board on behalf of Mark Kennedy and Winifred Wheeler, owners of 510 College Avenue, who seek a special exception to use the property for a student home. The Applicant is requesting a determination from the Board that the proposed use is consistent with the Township's Comprehensive Plan. There are six conditions which must be satisfied in order for the special exception to be approved and the Applicant intends to comply with all of those conditions.

Some of the items discussed by the Board included adjacent land uses, number of students who will be living on the property (limited to 3 by the Township Code) and how that number will be controlled/enforced, general concerns about the impacts created by student housing in a residential neighborhood, location, if any, of any other student homes in the vicinity of this site, general requirements related to required parking and buffers and other structures on the site (pool, pool house and storage building) and their proposed use

# Mr. Capuzzi makes a motion to find that the proposed use is in compliance with the Township's 1988 Comprehensive Plan subject to the following conditions:

- 1. The Applicant shall comply with all of the requirements applicable to a student home use contained in Sections 182-707 and 182-718 of the Township Zoning Ordinance;
- 2. Any additional plantings and landscaping that may be required to provide the required buffer for the parking area shall be reviewed and approved by the shade Tree Commission; and
- 3. All parking spaces for the proposed use shall be located to the side and/or rear of the existing building.

#### Mr. Reardon seconds the motion

Motion Fails by a vote of 2-2 (Mr. Fiorimondo and Mr. Pointon oppose)

# Item #5 Indoor Recreational Facility- 1025 West Chester Pike Review for conformance with the Comprehensive Plan

A Zoning Application has been filed on behalf of Lisa Isaacs Trustee of the Emerick and Edith Ressler Trust, equity owner of 1025 West Chester Pike. Applicant seeks a special exception to use the property for a Brazilian Jiu Jitsu facility. The property is zoned C-3 and was formerly used as a retail establishment.

Mr. Capuzzi makes a motion to find that the proposed use is in compliance with the Township's 1988 Comprehensive Plan.

Mr. Pointon seconds the motion

Motion passes 4-0

Item #6 Review of Minutes

Approval of the minutes from the Planning Commission's meeting of January 24, 2019 is tabled until the next meeting.

Mr. Reardon makes a motion to adjourn the meeting.

Mr. Capuzzi seconds this motion.

Motion passed 4-0.

**ADJOURNMENT** 

angelom. Capusés 6/13/19



May 9, 2019 | 7:30 p.m. Haverford Township Municipal Services Building 1014 Darby Road, Havertown, PA 19083

# Planning Commission Members:

Angelo Capuzzi, Chairman | Chuck Reardon, Vice Chairman | Christian Gaumann, Secretary | Paul D'Emilio | Robert Fiordimondo | Jesse Pointon | Joseph Russo

#### Others in Attendance:

Chuck Faulkner, Pennoni Assoc. | Kelly Kirk, Zoning Officer & Community Planner | Lisa Favacchia, Recording Secretary

## Agenda Items

## 1. Opening of Meeting

- a. Roll Call
- b. Pledge of Allegiance

# 2. Planning Commission Recommendation- Grant Application

PA Department of Community & Economic Development- Greenways, Trails & Recreation Program 224 Foster Avenue- Community Dog Park

Grant Application in the amount of \$250,000 from the Commonwealth Financing Authority to be used for the acquisition of 224 Foster Avenue and the redevelopment of that property into a Community Dog Park

# 3. Planning Commission Recommendation- Grant Application

PA Department of Community & Economic Development- Greenways, Trails & Recreation Program Tributary Crossing to Accommodate Darby Creek Trail

Grant application in the amount of \$213,000 from the Commonwealth Financing Authority to be used for modifications to an unnamed tributary to Darby Creek to accommodate the future extension of the Darby Creek Trail.

# 4. Planning Commission Recommendation- Grant Application

PA Department of Community & Economic Development-Flood Mitigation Grant Program Proposed Underground Retention Facility- Chatham Glen Park

Grant application in the amount of \$500,000 from the Commonwealth Financing Authority to be used for the construction of an underground retention facility within Chatham Glen Park.

#### 5. Review of Minutes

## RESOLUTION NO. 2135-2019 Township of Haverford

# Greenways, Trails and Recreation Program (GTRP) 224 Foster Avenue

**NOW, THEREFORE, BE IT RESOLVED**, that Haverford Township hereby requests a Greenways, Trails and Recreation Program (GTRP) Grant in the amount of \$250,000 from the Commonwealth Financing Authority to be used for the acquisition of the property at 224 Foster Avenue and the redevelopment of the parcel into a Community Dog Park.

**BE IT FURTHER RESOLVED**, that the Board of Commissioners does hereby designate David R. Burman (Township Manager/Secretary) as the official to execute all documents and agreements between the Township and the Commonwealth Financing Authority to facilitate and assist in obtaining the requested grant.

RESOLVED this 13th day of May, A.D., 2019

# **TOWNSHIP OF HAVERFORD**

	BY:	
	Andy Lewis, President Board of Commissioners	
ATTEST:		
David R. Burman Township Manager/Secretary		

# RESOLUTION NO. 2136-2019 Township of Haverford

Greenways, Trails and Recreation Program (GTRP)
Tributary Crossing to Accommodate Darby Creek Trail

**NOW, THEREFORE, BE IT RESOLVED**, that Haverford Township hereby requests a Greenways, Trails and Recreation Program (GTRP) Grant in the amount of \$213,000 from the Commonwealth Financing Authority to be used for modifications to an unnamed tributary to Darby Creek to accommodate the future extension of the Darby Creek Trail.

**BE IT FURTHER RESOLVED**, that the Board of Commissioners does hereby designate David R. Burman (Township Manager/Secretary) as the official to execute all documents and agreements between the Township and the Commonwealth Financing Authority to facilitate and assist in obtaining the requested grant.

RESOLVED this 13th day of May, A.D., 2019

TOWNSHIP OF HAVERFORD

	BY:	
	Andy Lewis, President	
	Board of Commissioners	
ATTEST:		
David R. Burman		
Township Manager/Secretary		

# RESOLUTION NO. 2137-2019 Township of Haverford

# Flood Mitigation Program (FMP) Proposed Underground Retention Facility – Chatham Glen Park

**NOW, THEREFORE, BE IT RESOLVED**, that Haverford Township hereby requests a Flood Mitigation Program (FMP) Grant in the amount of \$500,000 from the Commonwealth Financing Authority to be used for the construction of an underground retention facility at the Chatham Glen Park.

**BE IT FURTHER RESOLVED**, that the Board of Commissioners does hereby designate David R. Burman (Township Manager/Secretary) as the official to execute all documents and agreements between the Township and the Commonwealth Financing Authority to facilitate and assist in obtaining the requested grant.

RESOLVED this 13th day of May, A.D., 2019

**TOWNSHIP OF HAVERFORD** 

	BY: Andy Lewis, President	
	Board of Commissioners	
ATTEST:		
David R. Burman Township Manager/Secretary		

# Planning Commission Meeting Minutes Thursday, May 9, 2019

Minutes of the meeting of the Planning Commission of Haverford Township held on Thursday, May 9, 2019 at 7:30 p.m. in the Commissioners' Meeting Room (201B), Haverford Township Municipal Services Building, 1014 Darby Road, Havertown, PA 19083.

#### **BOARD MEMBERS PRESENT:**

#### **BOARD MEMBERS NOT PRESENT:**

Joe Russo, Member

Angelo Capuzzi, Chairman Chuck Reardon, Vice-Chairman Chris Gaumann, Secretary Robert Fiordimondo, Member Jesse Pointon, Member

# ALSO PRESENT:

Kelly Kirk, Zoning Officer & Community Planner Chuck Faulkner, Pennoni Associates

# 1. Opening of Meeting

Mr. Capuzzi called the meeting to order at 7:31 p.m.

- a. Roll Call
- b. Pledge of Allegiance

# 2. Planning Commission Recommendation- Grant Application

224 Foster Avenue- Community Dog Park

PA Department of Community & Economic Development-

Greenways, Trails & Recreation Program

The property has suffered from chronic flooding, despite remedial efforts. This grant application has been amended to propose a greenway/open space in lieu of a dog park.

Mr. Capuzzi made a Motion to recommend pursuing a grant in the amount of \$250,000 from the Commonwealth Financing Authority to be used for the acquisition of 224 Foster Avenue and the redevelopment of that property into a greenway/open space area and determined the proposal is consistent with the Comprehensive Plan of Haverford Township.

Mr. Reardon seconded the Motion.

Roll call vote was taken

MOTION PASSED UNANIMOUSLY.

# 3. Planning Commission Recommendation- Grant Application Tributary Crossing to Accommodate Darby Creek Trail

PA Department of Community & Economic Development-

Greenways, Trails & Recreation Program

The Darby Creek Trail Feasibility Study performed by Pennoni Associates in December 2017 proposed the extension of an existing culvert to allow for easier pedestrian access.

This area is currently being utilized as an unofficial segment of the trail.

Mr. Capuzzi made a Motion to recommend pursuing a grant in the amount of \$213,000 from the Commonwealth Financing Authority to be used for modifications to an unnamed tributary to

Darby Creek to accommodate the future extension of the Darby Creek Trail and determined the proposal is consistent with the Comprehensive Plan of Haverford Township. .

Mr. Gaumann seconded the Motion.

Roll call vote was taken

MOTION PASSED UNANIMOUSLY.

# 4. Planning Commission Recommendation- Grant Application Proposed Underground Retention Facility- Chatham Glen Park

PA Department of Community & Economic Development-

Flood Mitigation Grant Program

The Chatham Glen neighborhood has historically suffered from flooding during heavy rainstorms due to its lower elevation and underground tributaries to Cobbs Creek. This grant will provide for an underground retention facility within the limits of Chatham Glen Park to further address the on-going issue.

Mr. Capuzzi made a Motion to recommend pursuing a grant in the amount of \$500,000 from the Commonwealth Financing Authority to be used for the construction of an underground retention facility within Chatham Glen Park and determined the proposal is consistent with the Comprehensive Plan of Haverford Township.

Mr. Gaumann seconded the Motion.

Roll call vote was taken

MOTION PASSED UNANIMOUSLY.

### 5. Review of Minutes

No minutes were submitted for review at this meeting.

# Adjournment

Mr. Reardon made a Motion to adjourn the meeting at 7:45 p.m.

Mr. Pointon seconded the Motion.

MOTION PASSED UNANIMOUSLY.



June 13, 2019 7:30 p.m. Haverford Township Municipal Services Building 1014 Darby Road, Havertown, PA 19083

# Planning Commission Members:

Angelo Capuzzi, Chairman | Chuck Reardon, Vice Chairman | Christian Gaumann, Secretary | Paul D'Emilio | Robert Fiordimondo | Jesse Pointon | Joseph Russo

#### Others in Attendance:

Chuck Faulkner, Pennoni Assoc. | Kelly Kirk, Zoning Officer & Community Planner | Lisa Favacchia, Recording Secretary

# Agenda Items

## 1. Opening of Meeting

- a. Roll Call
- b. Pledge of Allegiance

# 2. 850 N. Eagle Road- Mr. Storage

Preliminary/Final Land Development & Lot Line Change Plan

Proposed minor subdivision to transfer 27,850 square feet of land from 1315 Lawrence Road Holdings, LP to Haverford Mr. Storage for the purpose of a 11,645 square foot addition.

### 3. 217 Walnut Hill Lane- Terrador Penn, LLC

Sewer Facilities Planning Module

Proposed sewage facilities planning module for the addition of one EDU in the Darby Creek Drainage System, associated with the subdivision of the property at 217 Walnut Hill Lane.

#### 4. Review of Minutes



June 27, 2019 7:30 p.m. Haverford Township Municipal Services Building 1014 Darby Road, Havertown, PA 19083

# Planning Commission Members:

Angelo Capuzzi, Chairman | Chuck Reardon, Vice Chairman | Christian Gaumann, Secretary | Paul D'Emilio | Robert Fiordimondo | Jesse Pointon | Joseph Russo

#### Others in Attendance:

Chuck Faulkner, Pennoni Assoc. | Kelly Kirk, Zoning Officer & Community Planner | Lisa Favacchia, Recording Secretary

# Agenda Items

## 1. Opening of Meeting

- a. Roll Call
- b. Pledge of Allegiance

# 2. 301-305 Ellis Road- RS Homes, LLC

Preliminary/Final Minor Subdivision Plan

Applicant proposes to demolish the existing single-family dwelling and subdivide the 2.0422 acre parcel into two lots. Proposed Lot #1 will contain 1.0413 acres, and proposed Lot #2 will contain 1.0008 acres. The construction of a new single-family dwelling and associated stormwater management facilities are proposed for each parcel.

#### 3. Review of Minutes



July 25, 2019 7:30 p.m. Haverford Township Municipal Services Building 1014 Darby Road, Havertown, PA 19083

# Planning Commission Members:

Angelo Capuzzi, Chairman | Chuck Reardon, Vice Chairman | Christian Gaumann, Secretary | Robert Fiordimondo | Jesse Pointon | Joseph Russo

#### Others in Attendance:

Chuck Faulkner, Pennoni Assoc. | Kelly Kirk, Zoning Officer & Community Planner | Lisa Favacchia, Recording Secretary

# Agenda Items

## 1. Opening of Meeting

- a. Roll Call
- b. Pledge of Allegiance

# 2. 301-305 Ellis Road-RS Homes, LLC

Preliminary/Final Minor Subdivision Plan

Applicant proposes to demolish the existing single-family dwelling and subdivide the 2.0422 acre parcel into two lots. Proposed Lot #1 will contain 1.0413 acres, and proposed Lot #2 will contain 1.0008 acres. The construction of a new single-family dwelling and associated stormwater management facilities are proposed for each parcel.

### 3. 850 N. Eagle Road- Mr. Storage

Preliminary/Final Land Development & Lot Line Change Plan

Proposed minor subdivision to transfer 27,850 square feet of land from 1315 Lawrence Road Holdings, LP to

Haverford Mr. Storage for the purpose of an 11,645 square foot addition.

#### 4. Review of Minutes



October 10, 2019 | 7:30 p.m. Haverford Township Municipal Services Building 1014 Darby Road, Havertown, PA 19083

### Planning Commission Members:

Angelo Capuzzi, Chairman | Chuck Reardon, Vice Chairman | Christian Gaumann, Secretary | E. David Chanin | Robert Fiordimondo | Jesse Pointon | Joseph Russo

#### Others in Attendance:

Chuck Faulkner, Pennoni Assoc. | Kelly Kirk, Zoning Officer & Community Planner | Lisa Favacchia, Recording Secretary

#### **Agenda Items**

- 1. Opening of Meeting
  - a. Roll Call
  - b. Pledge of Allegiance

## 2. 1417 Fairview Road-Ormond Properties, LLC

PA DEP Sewage Facilities Planning Module

Component 4A- Municipal Planning Agency Review

Applicant proposes to connect one new home to the existing public sewer. Estimated sewage flow will be 262.5 gpd for the one new home on the site at 262.5 gpd per house. A sewer main tap-in with new lateral is proposed to tie the new home into the existing sanitary sewer in Fairview Avenue.

### 3. 1400 Ellston Road- Ormond Properties, LLC

PA DEP Sewage Facilities Planning Module

Component 4A- Municipal Planning Agency Review

Applicant proposes to connect one new home to the existing public sewer. Estimated sewage flow will be 262.5 gpd for the one new home on the site at 262.5 gpd per house. A sewer main tap-in with new lateral is proposed to tie the new home into the existing sanitary sewer in Peach Lane.

### 4. Chapter 160, Subdivision and Land Development Ordinance Amendment

Discussion of proposed revisions to Chapter 160 relating to subdivision and land development projects.

#### 5. Review of Minutes

# **AGENDA**

# Haverford Township Planning Commission Meeting

December 12, 2019 | 7:30 p.m. Haverford Township Municipal Services Building 1014 Darby Road, Havertown, PA 19083

# Planning Commission Members:

Angelo Capuzzi, Chairman | Chuck Reardon, Vice Chairman | Christian Gaumann, Secretary | E. David Chanin | Robert Fiordimondo | Jesse Pointon | Joseph Russo

### Others in Attendance:

Kelly Kirk, Zoning Officer & Community Planner

### Agenda Items

- 1. Opening of Meeting
  - a. Roll Call
  - b. Pledge of Allegiance
- 2. Chapter 160, Subdivision and Land Development Ordinance Amendment

Discussion of proposed revisions to Chapter 160 relating to subdivision and land development projects.

3. Review of Minutes

#### **ORDINANCE NO. P2-2020**

AN ORDINANCE OF THE TOWNSHIP OF HAVERFORD, DELAWARE COUNTY, PENNSYLVANIA, AMENDING AND SUPPLEMENTING ORDINANCE NO. 1960, ADOPTED JUNE 30, 1986, AND KNOWN AS THE "GENERAL LAWS OF THE TOWNSHIP OF HAVERFORD", ADOPTED JUNE 30, 1986, FURTHER AMENDING, CHAPTER 160 "SUBDIVISION AND LAND DEVELOPMENT."

BE IT ENACTED AND ORDAINED by the Board of Commissioners of the Township of Haverford, County of Delaware, Commonwealth of Pennsylvania, and it is hereby enacted and ordained by the authority of the same that the General Laws of the Township of Haverford (the "General Laws"), is hereby amended as follows:

#### **SECTION 1.** TEXT AMENDMENTS

Article II. Procedures and Requirements

Chapter 160, Section 160-4, *Plan procedures and requirements*, subsection E, Preliminary plans, is hereby amended as follows:

- (5) Preliminary plan submission requirements for major subdivision and land development plans. Each preliminary plan shall show the following or be accompanied by such supplementary information:
  - (e) Existing physical or other features, including but not limited to:
    - [4] All storm drainage, sanitary sewer and public water supply lines or facilities and other public utilities within 400 100 feet of the site and including ownership or and/or maintenance responsibilities for the same.
  - (g) The proposed layout of the major subdivision or land development area, including, where appropriate for either:
    - [9] Building setback lines established by zoning the Zoning Chapter or other ordinances.
    - [14] The open space requirements for all subdivision and land developments as contained in the Zoning Chapter §160-5C shall be reflected on any preliminary plan submitted to the Township.

Chapter 160, Section 160-4, *Plan procedures and requirements*, subsection F, Final plan procedures and requirements for major subdivision and land development plans, is hereby amended as follows:

(1) Procedures. The procedures, reviews and fees of final plans shall be identical to those outlined in Subsection E, except as follows:

(b) In addition to the copies of prints therein required, the applicant/developer shall supply, upon request, two linen/Mylar originals an electronic copy of the final plan.

Article III: Required Improvement and Design Standards

Chapter 160, Section 160-5, *General Purpose and applicability; design standards*, subsection B, General design standards, is hereby amended as follows:

- (2) Preservation of environment.
  - (i) A minimum of 80% of the buildable area provided on each lot created by subdivision shall be unencumbered by steep slope, floodplain, and/or wetland areas.
- (4) Design criteria and requirements for curbs, sidewalks and streetlighting.
  - (c) Sidewalks shall be required where, in the opinion of the Board of Township Commissioners, heavy pedestrian traffic will result or where pedestrian safety requires such sidewalks. for all subdivision and land development proposals. Sidewalks are required for any multifamily development.
  - (f) Streetlighting shall be required for all nonresidential land developments, for all multifamily residential areas and, at the discretion of the Board of Commissioners, for all or portions of certain single-family residential major subdivisions. As a minimum in single-family subdivisions, appropriate conduit with pull wires shall be installed underground even though standards and lighting fixtures may not be constructed immediately. Proposed intersections with any major collector street or major arterial shall have streetlights.
- (9) Sanitary sewers.
  - (b) In accordance with Chapter 149, Sewage and Drainage Facilities, sanitary sewers shall be installed and connected to the Township sanitary sewer system. If outfall sewers are not available but are planned and have been scheduled in the Township's capital improvement program for the area in question, a system of sewers, together with all necessary laterals extending from the main sewer to the street right-of-way line, shall be installed and capped. The Board of Commissioners may waive the above requirements for lots of one acre or larger if sewage disposal is accomplished through land treatment technologies capable of recharging groundwater aquifers.
  - (h) On-site sewage disposal facilities. Whenever it is impracticable to connect with Township sewers, on- On-site sewage disposal facilities

may be permitted upon application and approval by the Sewage Enforcement Officer of the Township of Haverford and the Pennsylvania Department of Environmental Resources. Such facilities shall be so located as to permit easy and economical connection to the sewer system of the Township when sewers are installed, except where this requirement is waived under Subsection B(9)(b) above. The type of private sewage disposal system to be installed shall be determined by the results of percolation tests, soil classification and depth of water table, which shall be determined according to the size of the lot. Proof of the adequacy of such facilities shall be furnished by a registered professional engineer or other qualified person. The reports of such tests shall be required at each disposal area, except for large tracts involving more than one disposal system, in which case the prescribed tests shall be made in the amount of one per acre or as designated by the Sewage Enforcement Officer and the Pennsylvania Department of Environmental Resources.

#### **SECTION 2.** SEVERABILITY

Should any section, sentence, word or provision of this ordinance be declared by a Court of competent jurisdiction to be invalid, such decision shall not affect the validity of this Ordinance as a whole.

#### **SECTION 3.** REPEALER

Any ordinance or part of ordinance to the extent that it is inconsistent herewith is hereby repealed.

ADOPTED this of	, A.D., 2020.
	TOWNSHIP OF HAVERFORD
	BY: President Board of Commissioners

ATTEST:

David R. Burman Township Manager/Secretary